TECHNOLOGY OF **ASSACHUSETTS**

APULLO

GUIDANCE, NAVIGATION AND CONTROL

R-693

GUIDANCE SYSTEM OPERATIONS PLAN FOR MANNED CM EARTH ORBITAL MISSIONS USING PROGRAM SKYLARK 1

SECTION 7 ERASABLE MEMORY PROGRAMS

March 1973

MIT

CHARLES STARK DRAPER
LABORATORY

CAMBRIDGE MASSACHUSETTS 02139



GUIDANCE, NAVIGATION AND CONTROL

Submitted by: M. H. HAMILTON, DIRECTOR, MISSION PROGRAM DEVEL.

APOLLO GUIDANCE AND NAVIGATION PROGRAM

Approved: Date: 3 30 73

R. A. LARSON, SKYLARK PROJECT MANAGER
APOLLO GUIDANCE AND NAVIGATION PROGRAM

Approved: Date: 5/30/73

R. H. BATTIN, DIRECTOR, MISSION DEVELOPMENT
APOLLO GUIDANCE AND NAVIGATION PROGRAM

Approved: Date: 5/30/73

D. G. HOAG, DEPUTY DIRECTOR
CHARLES STARK DRAPER LABORATORY

R-693

GUIDANCE SYSTEM OPERATIONS PLAN FOR MANNED CM EARTH ORBITAL MISSIONS USING PROGRAM SKYLARK 1

SECTION 7 ERASABLE MEMORY PROGRAMS

March 1973



ACKNOWLEDGEMENT

This report was prepared under DSR Project 55-23890, sponsored by the Manned Spacecraft Center of the National Aeronautics and Space Administration through Contract NAS 9-4065.

GUIDANCE SYSTEM OPERATIONS PLAN FOR MANNED CM EARTH ORBITAL MISSIONS USING PROGRAM SKYLARK 1

SECTION 7 ERASABLE MEMORY PROGRAMS

Signatures appearing on this page designate approval of this document by NASA/MSC.

| | 1. 6. |
|---|---------------|
| Approved: | Date: 3/16/73 |
| John R. Garman Section Chief, Guidance Program Section Manned Spacecraft Center, NASA | |
| Approved: Ilm E. William | Date: 3/14/15 |
| John B. Williams, Jr. | , , |
| Chief, Simulation and Flight Software Branch Manned Spacecraft Center, MASA / | |
| Wallied Spaceerate center, 19161 | 1 / |
| Approved: | Date: 3/19/23 |
| James V. Stokes, Jr. | |
| Chief, Flight Support Division | |
| Manned Spacecraft Center, NASA | |

TABLE OF CONTENTS

| EMP NO. | TITLE |
|---------|---|
| | Introduction |
| SL-1 | Recover Angle PHI at T _D |
| SL-2 | Software Restart |
| SL-3 | GDC REFSMMAT Determination |
| SL-4 | Backup Optics Variance |
| SL-5 | Mark Taking With a Mark/Mark Rej. Input Channel Bit Failure |
| SL-6 | DSKY Display of VHF Range During P37 |
| SL-9 | Inhibit Gimbal Lock Monitor Downmoding |
| SL-15 | Manual Range Input |
| SL-21 | Enter P51/P53 With IMU-Operate Bit Failed Off |
| SL-22 | SPS Gimbal Drive Test |
| SL-23 | Monitor Jet-On Failure |
| SL-26 | IMU CDU Transient Monitor |
| SL-27 | Monitor Single IMU CDU |
| SL-28 | Monitor Jet-On Failure and Do EMP SL-26 |
| SL-50 | Convert Gyro Torquing Angles to CDU Angles for Failed IMU |
| SL-51 | Generalized Rotational Rate Generator |
| SL-52 | CHECKSUM for EMPs Using VAC Area 4 |

NOTE: The Erasable Memory Programs (EMP) contained in this section are individually paginated within each EMP.

INTRODUCTION

GENERAL

Section 7 of the Guidance System Operations Plan (GSOP) describes erasable-memory programs (EMPs) designed for the guidance computer used in the command module (CMC) program SKYLARK 1.

The EMPs vary in complexity from a simple flagbit setting to a long and intricate logical structure. They all, however, cause the computer to behave in a way not intended in the original design of the programs; they accomplish this off-nominal behavior by some alteration of erasable memory to interface with existing fixed-memory programs to effect a desired result.

<u>CAUTION</u>.—Great care must be taken when loading or performing an EMP. An erroneous digit loaded into NOUN 26, for example, could cause indeterminate operation upon program initiation.

NOTE 1.—The EMPs described in this section should not be run simultaneously except when explicitly specified.

NOTE 2.—Level-6 performance-evaluation testing has not been performed on EMPs.

NOTE 3, —If an EMP is to be recalled all procedures should be repeated, unless the EMP specifically gives alternate procedures for recalling the EMP.

NOTE 4.—Under RESTRICTIONS & LIMITATIONS the restriction in the use of self-check also includes V91 (BANKSUM). (See GSOP Section 1 of R-577.)

The following format is used throughout this section:

NUMBER AND NAME OF EMP.

PURPOSE.

FUNCTIONAL DESCRIPTION—a brief description of the EMP and how it interfaces with fixed-memory programs (may include a functional-flow diagram).

ASSUMPTIONS-prerequisite conditions and configurations.

RESTRICTIONS AND LIMITATIONS—conditions and operations that would interfere with, or be affected by, the EMP.

PROCEDURES—instructions for performing the EMP.

RECOVERY/TERMINATION—procedures for terminating the EMP or recovering from a hardware or software restart.

ERASABLE MEMORY—listing of memory locations (octal) and the code (mnemonic and octal) comprised by the EMP.

UPLINK-P27 format for loading the EMP into erasable memory.

JOBS AND TASKS

A number of EMPs are initiated by VERB 30 ENTR (Request Executive) or VERB 31 ENTR (Request WAITLIST). When the EMP is programed as a JOB, the activation procedures specify VERB 30 ENTR; when the EMP is programed as a TASK, the procedures specify VERB 31 ENTR. The distinction is on the basis of how the program is dispatched. A JOB carries a priority; when the JOB's priority comes up on the executive queue, the JOB is activated. A TASK differs in that it is performed as a T3-clock interrupt. The AGC WAITLIST program sets the T3 clock to overflow at a specified time; when the overflow occurs, other program activity is interrupted, and the TASK is performed.

For VERB 30 use, the JOB's priority is specified in R1 of NOUN 26. R1 of NOUN 26 also contains in the low-order digit an indication of whether or not the JOB is to be assigned a VAC area: if the low-order digit is "1," a VAC area is reserved for the JOB; if it is "0," no VAC area is reserved.

For VERB 31 use, R1 of NOUN 26 must contain the time specified to elapse (in centiseconds) between the keying of ENTR (after VERB 31) and TASK execution.

EMPs activated by VERB 30 ENTR (i.e., JOB EMPs) require NOUN 26 to be loaded as follows:

```
R1 = xx00y<sub>8</sub>
where
xx_8 = JOB \text{ Priority}
y = 1 \text{ designates a VAC JOB;}
y = 0 \text{ designates a NOVAC JOB.}
R2 = xxxxx<sub>8</sub>
where
xxxxx_8 \text{ is the JOB starting address}
```

xxxxx₈ is the BBCON, containing the fixed, super, and erasable banks associated with the JOB

EMPs activated by VERB 31 ENTR (i.e., TASK EMPs) require NOUN 26 to be loaded as for a JOB EMP, except that R1 contain not a JOB priority, but a time delay as described above:

R1 =
$$xxxxx_8$$
 cs delay
R2 = $xxxxx_8$ starting address
R3 = $xxxxx_8$ BBCON

The BBCON is packed as follows:

F-banks $00-27_8$ are addressed independently of S-bank contents; F-banks $30-37_8$ are addressed for S-bank values of 3_8 or less, and F-banks $40-43_8$ are addressed for an S-bank value of 4_8 :

Example 1

Example 2

Example 3

Coding for EMPs can be loaded into VAC areas. These erasable registers are assigned by the AGC Executive when a job (fixed or erasable memory) requires scratch storage for vector arithmetic. To reserve a VAC area its first register is set to zero. A Fresh Start, Restart or Major Mode change will set the first register of each VAC area to its erasable memory address, making it available for assignment to a job. Hence, if a large amount of job activity takes place after a Fresh Start, Restart or Major Mode change, it is possible that the EMP code loaded into a VAC area could be overwritten. EMP SL-52 provides a means of determining whether or not EMP coding previously loaded into a VAC area is still intact.

DOWNLINK

Listed below are the EMPs and the particular downlist transmitted during the operation of each EMP:

| EMP | | Downlist | |
|-------|-----|-------------------------------------|--|
| SL-1 | | Rendezvous and Prethrust List | |
| SL-2 | | Any | |
| SL-3 | | Coast and Align List | |
| SL-4 | | Rendezvous and Prethrust List | |
| SL-5 | P20 | Rendezvous and Prethrust List | |
| | P5x | Coast and Align List | |
| SL-6 | | Rendezvous and Prethrust List | |
| SL-9 | | Any | |
| SL-15 | | Rendezvous and Prethrust List | |
| SL-21 | | Coast and Align List | |
| SL-22 | | Any | |
| SL-23 | | Any but Powered List | |
| SL-26 | | Any but Rendezvous & Prethrust List | |
| SL-27 | | Any | |
| SL-28 | | Coast and Align List | |
| SL-50 | | Coast and Align List | |
| SL-51 | P00 | Coast and Align List | |
| | P20 | Rendezvous and Prethrust List | |
| | P47 | Powered List | |
| SL-52 | | Any | |
| | | | |

EMP SL-1: RECOVER ANGLE PHI AT TD

PURPOSE:

EMP SL-1 provides a means for recovering the elevation angle ϕ in NOUN 77 if Skylark Anomaly SKY-001 has occurred, i.e., computation of ϕ_{t} is bypassed.

FUNCTIONAL DESCRIPTION:

PHICOMP is a fixed memory routine used to compute ϕ . It is normally called as a job by routine PHIJOB at the optimization time t_D . NOUN 26 is loaded with the priority of PHIJOB and the address of PHIJOB + 3. Thus, when VERB 30 is selected, PHICOMP computes ϕ for t_D , (regardless of the present time), clears SNAPFLAG, and terminates via ENDOFJOB.

ASSUMPTIONS:

- 1. R27 optimization interval has been entered for the time $$t_{\rm D}$^{\raisebox{3.5pt}{\text{\circle*{1.5}}}}$$
- 2. The crew has boresighted the SXT at t_D .
- 3. The anomaly has occurred: the code -00001 in R3 of NOUN 77 has not been overwritten with $\phi_{\rm tD}$ by the time $\rm t_D$ + 10 sec.

RESTRICTIONS AND LIMITATIONS:

- 1. Activation via VERB 30 ENTR not before $t_{\rm D}$ + 10 , and not after $t_{\rm D}$ + 85 sec.
- 2. A prethrust computation cycle will delay execution of EMP SL-1.
- 3. A restart during any computation of ϕ_{t_D} may result in an error in the angle ϕ_{t_D} due to the CDU snapshot following the restart. (See SKYLARK Anomaly SKY-002.)

PROCEDURES:

1. Key:

VERB 25 NOUN 26 ENTR

27001 ENTR

2410 ENTR | fixed-memory address 60002 ENTR | of PHIJOB + 3

2. After t_D + 10 sec, key VERB 30 ENTR RECOVERY/ TERMINATION:

NA

ERASABLE MEMORY:

NA

UPLINK:

EMP SL-2: SOFTWARE RESTART

PURPOSE:

EMP SL-2 provides a means of causing a software restart

by keying VERB 31 ENTR.

FUNCTIONAL DESCRIPTION:

EMP SL-2 uses existing fixed program code to perform

BAILOUT and store Alarm Code 31211.

ASSUMPTIONS:

NA

RESTRICTIONS

AND LIMITATIONS: NA

PROCEDURES:

1. Key-

VERB 25 NOUN 26 ENTR

1 ENTR

2055 ENTR | fixed memory address of

16000 ENTR | MKABORT

2. To affect software restart, key VERB 31 ENTR

3. Observe PROG alarm light

4. Key VERB 5 NOUN 9 ENTR to observe alarm code

31211, "Illegal interrupt of extended verb"

5. Key RSET to clear alarm

RECOVERY/

TERMINATION: NA

ERASABLE

MEMORY:

UPLINK:

NA NA

EMP SL-3: GDC REFSMMAT DETERMINATION

PURPOSE:

EMP SL-3 provides a means of using the gyro display coupler (GDC) to determine orientation of the spacecraft. This program establishes the inertial reference for performing rendezvous with an unusable IMU.

NOTE1.—EMP SL-3 complements EMPs SL-4 and SL-6 for performing rendezvous navigation with a failed IMU. No mission performance testing has been performed with this sequence.

NOTE2.—To perform REFSMMAT determination with failed IMU-OPERATE discrete failed off, use EMP SL-21.

FUNCTIONAL DESCRIPTION:

EMP SL-3 bypasses only the very first part of P51/P53 (see Figure: EMP SL-3), that part which determines whether the IMU is on and operating (bit 9 of IMODES30).

ASSUMPTIONS:

- 1. GDC is inertial
- 2. IMU is unusable

RESTRICTIONS
AND LIMITATIONS:

- 1. Inertial reference established by EMP SL-3 is valid for only one spacecraft orientation, i.e., the orientation of the spacecraft when the two P51/P53 star sightings are made. The same orientation must be maintained during rendezvous sightings.
- 2. Because the IMU is unusable, the AUTO and ATT. HOLD modes of the CSM-alone and Docked RCS DAPs will be inoperative. The FREE mode of the CSM-alone and Docked DAPs, however, can be used.

PROCEDURES:

To initiate EMP SL-3, perform the following:

1. Preliminary

a. Key VERB 96 ENTR to clear all program activity.

b. To set MODREG to decimal 51, key—
VERB 21 NOUN 1 ENTR
1204 ENTR
63 ENTR

to set MODREG to decimal 53, key—
VERB 21 NOUN 1 ENTR
1204 ENTR
65 ENTR

c. Key-

VERB 25 NOUN 26 ENTR

13001 ENTR

3266 ENTR | fixed-memory address
30005 ENTR | of P51AA

to set up for the call to P51/P53 bypassing
IMU-on check.

2. Activate

a. Key VERB 30 ENTR to start EMP SL-3 (and P51/P53)

NOTE.—If it is desired that the REFSMMAT calculated by P51/P53 approximate a valid GDC inertial-attitude description, key VERB 25 and load NOUN 20 as follows (before step 2b):

Key-VERB 25 NOUN 20 ENTR
±xxxxx ENTR
±xxxxx ENTR
±xxxxx ENTR

where R1 = GDC OGA to nearest 0.01 deg,
R2 = GDC IGA to nearest 0.01 deg,
R3 = GDC MGA to nearest 0.01 deg.

b. Perform normal P51/P53 star sightings and procedure, maintaining a fixed attitude

NOTE.—P51/P53 is activated when VERB 30 is selected in step 2a, but the mode lights will remain at 00 rather than displaying 51/53.

RECOVERY/ TERMINATION:

Normal P51/P53 restart and termination procedures.

NOTE. — Should a restart occur, the PROG registers will change to 51/53.

ERASABLE

MEMORY:

NA

UPLINK:




FIG: EMP SL-3

EMP SL-4: BACKUP OPTICS VARIANCE

PURPOSE:

EMP SL-4 compensates for increased uncertainty when processing optics data obtained with a degraded ISS or OSS by using ALTVAR in place of SXTVAR in R22.

FUNCTIONAL DESCRIPTION:

This procedure utilizes the erasable variable ALTVAR instead of the fixed memory SXTVAR as the a-priori estimate for the angular error variance per axis. Since ALTVAR is the variance used for COAS marks, clearing R21MARK (indicating COAS marking) forces ALTVAR to be used in place of SXTVAR when processing optics marks. Since R21MARK is cleared, MARKREJ causes FL VERB 51 to appear. Using VERB 86 ENTR the normal COAS mark reject procedure avoids the FL VERB 51.

NOTE. — EMP SL-4 complements EMPs SL-3 and SL-6 for performing rendezvous navigation with a failed IMU. No mission performance testing has been performed with this sequence.

ASSUMPTIONS:

- 1. SXT or SCT usable—may be immobile (if good IMU)
- 2. Good OCDUs
- Good MARK button or use EMP SL-5. 3.

RESTRICTIONS AND LIMITATIONS:

If EMP SL-4 is being used as complementary program to EMP SL-3 (failed IMU), spacecraft attitude during marking must be the same as that used in EMP SL-3 to establish inertial reference.

PROCEDURES:

1. If REFSMFLG (FLAGWRD3, BIT 13) is not set key-

> VERB 25 NOUN 7 ENTR 77 ENTR 10000 ENTR

1 ENTR

to set REFSMFLG and enable selection of P20.

- 2. In P20, key
 - a. VERB 25 NOUN 7 ENTR

76 ENTR

20000 ENTR

ENTR

to clear R21MARK (FLAGWRD2, BIT 14)

b. VERB 21 NOUN 1 ENTR

37777 ENTR

to set MARKINDX to POSMAX

c. VERB 21 NOUN 1 ENTR

1326 ENTR

31223 ENTR

to load OPTCADR with fixed-memory address of ENDPLAC +1.

3. Use normal P20 marking procedures.

NOTE, —MARK REJ will cause FL VERB 51 to appear. To clear FL VERB 51, key PRO. (VERB 86 ENTR can be used if desired to avoid causing FL VERB 51.)

RECOVERY/ TERMINATION:

1. Any VERB 37 ENTR xx ENTR or

VERB 25 NOUN 7 ENTR

76 ENTR

20000 ENTR

1 ENTR (sets R21MARK - FLAGWRD2, BIT 14).

2. Any VERB 37 ENTR xx ENTR or restart disables program. To reenable, repeat PROCEDURES.

ERASABLE MEMORY:

See PROCEDURES

UPLINK:

EMP SL-5: MARK TAKING WITH A MARK/MARK REJ INPUT CHANNEL BIT FAILURE

PURPOSE:

EMP SL-5 provides a general-purpose mark taking routine for use when the MARK/MARK REJ input channel bit has failed. Bit 6 of channel 16 is the mark bit and bit 7 of channel 16 is the mark reject bit.

FUNCTIONAL DESCRIPTION:

Normal program procedures are completed up to point when marking normally takes place (FL VERB 51 or P20 option 0 or 4). A VERB 31 ENTR will initiate the MARK function. The existing fixed-memory task MARKDIF is set up, and program operation will continue as if a normal mark had been taken.

ASSUMPTIONS:

EMP SL-5 is called when (see PROCEDURES) failure has occurred in the MARK input channel and all other optics functions are working properly.

RESTRICTIONS AND LIMITATIONS:

- 1. If the MARK or MARK REJ channel bit has failed intermittently on, then neither regular marking nor execution of EMP SL-5 can be relied on.
- 2. Refer to the following matrix for EMP SL-5 contingencies under combination MARK/MARK REJ fail conditions:

| | | MARK REJ bit valid or Failed Off | MARK REJ bit Failed On |
|----|-----------|--|--|
| IV | IARK bit | Use EMP SL-5 | EMP SL-5 |
| F | ailed Off | from NAV DSKY | cannot be used |
| IV | IARK bit | Follow PROCEDURES | Follow PROCEDURES |
| F | ailed On | Step 1 on the MAIN DSKY. Then depress any key on the NAV DSKY to effect a mark. | Step 1 on the MAIN DSKY. Then depress any key on the NAV DSKY to effect a mark. |

PROCEDURES:

1. Perform normal program procedures up to point when marking normally takes place (FL VERB 51 or P20 option 0 or 4).

Load NOUN 26 as follows: Key VERB 25 NOUN 26 ENTR

1 ENTR
2151 ENTR | fixed-memory address
16067 ENTR | of MARKDIF

NOTE.—The CDU transient-detection test (1218 PROG alarm) is less effective in EMP SL-5 than in normal marking.

3. Key VERB 31 ENTR to take mark. (The ENTR accomplishes the MARK.)

NOTE1.—Unless a monitor display is active or any new display is initiated by the program or crew, the VERB 31 will remain in the VERB lights. (A KEY REL will reestablish the program display, if any.) As long as VERB 31 is in the VERB lights, an ENTR will activate EMP SL-5 to accomplish a mark. If VERB 31 is not in the VERB lights, Step 3 must be repeated if a mark is desired.

NOTE2,—Normal MARK REJ procedures apply when EMP SL-5 is operating, subject to noted exceptions.

4. When marking has been completed, continue with normal procedures for the program in use.

RECOVERY/ TERMINATION:

- 1. Normal restart procedures apply.
- Terminate marking program normally after keying KEY REL, if necessary, to reestablish program display.

ERASABLE MEMORY:

NA

UPLINK:

EMP SL-6: DSKY DISPLAY OF VHF RANGE DURING P37

PURPOSE:

EMP SL-6 provides a means of displaying VHF range on the DSKY during Rendezvous Final Phase Program (P37).

NOTE.—EMP SL-6 complements EMPs SL-3 and SL-4 for performing rendezvous navigation with a failed IMU. No mission performance testing has been performed with this sequence.

FUNCTIONAL DESCRIPTION:

EMP SL-6 enables either R27 (VHF Range Rate Mark Processing Routine) or R22 (Rendezvous Tracking Data Processing Routine). These routines read VHF Range counter, thus allowing the raw range data stored in RM to be monitored.

ASSUMPTIONS:

- 1. P20 (option 0 or 4) operating
- 2. VHF locked on OWS
- 3. Either VHF range mark processing is enabled in R22 (by VERB 87 ENTR) or R27 is enabled (by VERB 76 ENTR or by manually setting R27FLAG).

RESTRICTIONS AND LIMITATIONS:

- 1. If VERB 87 ENTR has been keyed, state vector updating by VHF range data is allowed. Range display will change about once per minute.
- 2. If R27 is enabled, the range display will change about once every 5 seconds.
- 3. Astronaut-loaded monitor display (see PROCEDURES) blocks a possible VERB 06 NOUN 49 display. A response to FL VERB 06 NOUN 49 is necessary for further updating of range display.

PROCEDURES:

To initiate EMP SL-6 enable R27 or R22 by performing either step 1 or 2.

1. If R27 has not been enabled prior to MINKEY selection of P37, R27 must be enabled by setting R27FLAG manually.

Key

VERB 25 NOUN 7 ENTR

107 ENTR

4000 ENTR

1 ENTR

to set R27FLAG (FLGWRD11, BIT 12).

- To enable VHF range marking in R22, key VERB 87 ENTR.
- 3. To initiate VHF range display of erasable memory location RM.

key VERB 16 NOUN 2 ENTR

3663 ENTR or

VERB 16 NOUN 76 ENTR

4. Observe VHF range

R1, xxx.xx n.mi

 \underline{NOTE} .—If R1<0, range = 327.67 -|R1|. Range is displayed modulo 327.68 n.mi.

RECOVERY/ TERMINATION:

To disable EMP SL-6:
 Key VERB 88 ENTR to disable VHF marking.
 Key VERB 77 ENTR to disable R27.

2. If restart occurs, repeat steps 3 and 4 of procedures.

ERASABLE MEMORY:

NA

UPLINK:

EMP SL-9: INHIBIT GIMBAL LOCK MONITOR DOWNMODING

PURPOSE:

EMP SL-9 provides a means of inhibiting T4RUPT coarse alignment of the IMU when there is a runaway CDUZ.

FUNCTIONAL DESCRIPTION:

EMP SL-9 causes "GLOCKMON" to believe program is in SATURN thrusting flight, bypassing downmoding of IMU into Coarse Align mode if |CDUZ| > 85 deg.

ASSUMPTIONS:

NA

RESTRICTIONS AND LIMITATIONS:

- 1. R30 (VERB 82) data will refer to CSM at latest permanent state-vector time only.
- 2. Any VERB 37 ENTR xx ENTR while AVERAGEG is running (P1x, P4x, P6x) will disable EMP SL-9.
- 3. All translations will cause CSM-alone DAP to use LM-on filter gains.

NOTE1.—If CDU has failed, CSM-alone DAP and Docked DAP will not operate normally.

NOTE2.—LM-on attitude control remains in coding although it is not intended for use during SKYLAB.

- 4. TVC DAP does not operate normally.
- 5. ENTRY programs do not operate normally (AVERAGEG will not be enabled).
- 6. VERB 46 should not be selected. If the CSM-alone DAP is to run while SL-9 is in effect, the CSM-alone DAP should be loaded and turned on before the SL-9 procedures are performed.

NOTE.—VERB 45, however, can be selected while SL-9 is in effect i.e., a switchover from CSM-alone to Docked DAP can be performed while SL-9 is in effect. Also the docked deadband can be changed by an execution of VERB 44 followed by a VERB 45 ENTR.

7. EMP SL-9 deactivates the automatic moding to coarse align at gimbal angles greater than 85 deg; maneuvering the vehicle into the area of a real gimbal lock will cause an IMU dump, with possible permanent damage to the IMU.

PROCEDURES:

To initiate EMP SL-9-

- 1. Key VERB 48 ENTR and load NOUN 46 (R1) to 3xxxx.
- 2. Key VERB 34 ENTR to terminate R03 (do not key PRO).
- 3. Key-

VERB 25 NOUN 7 ENTR

75 ENTR

1 ENTR

1 ENTR

to set AVEGFLAG bit (FLAGWRD1, BIT 1).

NOTE.—This procedure will not inhibit the GIMBAL LOCK light from coming on.

RECOVERY/ TERMINATION:

To disable EMP SL-9-

- 1. Key VERB 48 ENTR and load NOUN 46 (R1) with desired configuration.
- 2. Reset AVEGFLAG bit as follows:

Key-

VERB 25 NOUN 7 ENTR

75 ENTR

1 ENTR

ENTR

ERASABLE

MEMORY: NA

UPLINK: NA

EMP SL-15: MANUAL RANGE INPUT

PURPOSE:

EMP SL-15 provides a means to manually input range data into the CMC for state vector updates by R22 in the event of a VHF ranging problem.

NOTE.—No mission performance testing has been performed with this EMP.

FUNCTIONAL DESCRIPTION:

After VERB 88 ENTR is executed to inhibit R22 from reading the VHF range and VERB 77 ENTR is executed to inhibit R27, a future value of range in nautical miles is loaded into location RM via VERB 21 NOUN 2 ENTR. When the actual range nears the value loaded into RM, VERB 30 is keyed. The ENTR key is depressed when the range loaded in RM is reached to execute EMP SL-15. The time the actual range is reached will be determined by monitoring the EMS range counter contents.

EMP SL-15 clears REFSMFLG to terminate R22, stores current time in MARKTIME, delays 5.12 seconds to allow time for R22 to terminate, and then restarts R22 (at RANGERD1) to process the mark data.

ASSUMPTIONS:

- 1. VHF range data cannot be acquired automatically by the CMC.
- 2. Program coding has been uplinked.

RESTRICTIONS AND LIMITATIONS:

- 1. EMP SL-15 cannot be executed while R22 is processing a mark (optics or range) or while R27 is operating.
- 2. Location 3663 cannot be reloaded until the last manual range mark is processed (Step 5 of PROCEDURES).
- 3. EMP SL-15 is overlayed by XSMD; therefore, the erasable program must be reloaded following the execution of P27, P40, P41, P52/P54 (options 1 or 2), or P52 for MINKEY plane change.

PROCEDURES:

1. Key VERB 88 ENTR to inhibit R22 VHF range processing.

- 2. Key VERB 77 ENTR to inhibit R27 VHF range processing.
- 3. Key VERB 5 NOUN 26 ENTR and verify that NOUN 26 is valid for EMP SL-15:

R1 26001

R2 00306

R3 70067

- 4. Wait for R22 to complete processing of last mark.

 [NOUN 45 (R1) mark counter will be incremented when mark is incorporated.]
- To load range into RM, key VERB 21 NOUN 2 ENTR 3663 ENTR ±xxxxx ENTR (xxx.xx n.mi., future value of range, where -163.83 < xxx.xx < +163.83)</p>

NOTE,—To load ranges between 163.83 n.mi. and 327.68 n.mi., a negative value of range, computed as follows, must be loaded:

Range (to be loaded) = Range (actual) -327.67 n.mi.

If the actual range is 327.67 n.mi., -0 must be loaded. Ranges greater than 327.67 n.mi. must be loaded

modulo 327.68 n.mi.

- 6. At a time prior to reaching the loaded range, key VERB 30.
- 7. At the time the actual range is reached, key ENTR to execute EMP SL-15.
- 8. To process another manual range mark, repeat steps 4-7.

RECOVERY/ TERMINATION:

EMP SL-15 is not restart protected. Depending upon where restart occurs, the following will result:

- If R22 has started processing the mark, processing will continue normally.
- If the restart occurs while REFSMFLG is off, P20 will terminate and the mark will be lost. To examine REFSMFLG, key VERB 1 NOUN 1 ENTR, 77 ENTR

If BIT 13 = 0, reenable P20: a. Set REFSMFLG (FLAGWRD3, BIT 13)—

Key VERB 25 NOUN 7 ENTR
77 ENTR
10000 ENTR
1 ENTR

b. Reselect P20.

ERASABLE MEMORY:

Program coding for EMP SL-15 is as follows:

| ECADR | Tag | Cod | <u>de</u> | Octal |
|-------|---------|--------|-----------|-------|
| 1016 | N26/PRI | OCT | 26001 | 26001 |
| 1017 | | OCT | 306 | 306 |
| 1020 | | OCT | 70067 | 70067 |
| 306 | | EXTEND | | 00006 |
| 307 | | DCA | TIME2 | 30025 |
| 310 | | DXCH | MARKTIME | 53116 |
| 311 | | TC | DOWNFLAG | 07722 |
| 312 | | ADRES | REFSMFLG | 00057 |
| 313 | | CAF | BIT10 | 34770 |
| 314 | | TC | BANKCALL | 04647 |
| 315 | | CADR | E/BKCALL | 24000 |
| 316 | | CADR | DELAYJOB | 01731 |
| 317 | | TC | UPFLAG | 07710 |
| 320 | | ADRES | REFSMFLG | 00057 |
| 321 | | CA | RETURN | 30324 |
| 322 | | TS | RREADRET | 54363 |
| 323 | | TC | RANGERD1 | 03363 |
| 324 | RETURN | OCT | 70700 | 70700 |

UPLINK:

P27 uplink for loading CMC erasable memory for EMP SL-15 is as follows:

| Load 1 | Load 2 |
|--------|--------|
| V71E | V71E |
| 5 E | 21E |
| 1016E | 306E |
| 26001E | 6E |
| 306E | 30025E |
| 70067E | 53116E |
| V33E | 7722E |
| | 57E |
| | 34770E |
| | 4647E |
| | 24000E |
| | 1731E |
| | 7710E |
| | 57E |
| | 30324E |
| | 54363E |
| | 3363E |
| | 70700E |
| | V33E |

EMP SL-21: ENTER P51/P53 WITH IMU-OPERATE BIT FAILED OFF

PURPOSE:

EMP SL-21 provides a means of entering the IMU Orientation Determination Program (P51), or its backup (P53), when the IMU-operate bit has failed in the off state. (Channel 30, Bit 9 = 1.)

NOTE.—To perform REFSMMAT determination (P51/P53) with unusable IMU, use EMP SL-3.

FUNCTIONAL DESCRIPTION:

EMP SL-21 bypasses only the very first part of P51/P53 (see Figure: EMP SL-21), that part which determines whether the IMU is on and operating (bit 9 of IMODES30).

ASSUMPTIONS:

1. IMU is inertial.

NOTE.—If the IMU-operate bit has failed, checklist procedures should be performed to enable IMU failure and RCS DAP.

2. CDUs reflect vehicle attitude with respect to IMU.

RESTRICTIONS
AND LIMITATIONS:

NA

PROCEDURES:

To initiate EMP SL-21, perform the following:

- 1. Key VERB 96 ENTR to clear all program activity.
- 2. To set MODREG to decimal 51, key-

VERB 21 NOUN 1 ENTR 1204 ENTR 63 ENTR

to set MODREG to decimal 53, key-

VERB 21 NOUN 1 ENTR 1204 ENTR 65 ENTR

3. Key-

VERB 25 NOUN 26 ENTR

13001 ENTR

3266 ENTR | fixed-memory address

30005 ENTR | of P51AA

to set up for the call to P51/P53 bypassing IMU-on check.

- 4. Key VERB 30 ENTR to start EMP SL-21 (and P51/P53).
- 5. Perform normal P51/P53 star sightings and procedure.

NOTE.—P51/P53 is activated when VERB 30 is selected in step 4, but the PROG registers will remain at 00 rather than displaying 51/53.

RECOVERY/ TERMINATION:

Normal P51/P53 restart and termination procedures.

NOTE.—Should a restart occur the PROG registers will change to 51/53.

ERASABLE MEMORY:

NA

UPLINK:




FIG: EMP SL-21

EMP SL-22: SPS GIMBAL DRIVE TEST

PURPOSE:

This EMP permits the SPS Gimbal Drive Test to be performed without calling P40.

FUNCTIONAL DESCRIPTION:

After loading certain erasables and NOUN 26 through the DSKY (see PROCEDURES), the crew calls EMP SL-22 via VERB 31 ENTR. The existing SPS Gimbal Drive Test Routine (S40.6) in P40 is immediately executed as a task. (See Figure 3.3.1 of R-693, Section 3 GSOP.

ASSUMPTIONS:

- 1. Valid SPS engine-bell trim angles have been loaded via R03.
- 2. Checklist procedures for SPS engine gimbal use have been performed.

RESTRICTIONS AND LIMITATIONS:

This EMP should not be performed while in P40.

PROCEDURES:

 To initialize erasable locations MRKRTMP and CNTR, key—

VERB 25 NOUN 1 ENTR

3051 ENTR 1 ENTR ENTR ENTR

2. Key VERB 25 NOUN 26 ENTR

1 ENTR
2323 ENTR | fixed-memory address
40066 ENTR | of S40.6

- 3. Key VERB 31 ENTR to call EMP SL-22.
- 4. Monitor Gimbal Drive Sequence by reference to analog dials.
- 5. Key VERB 37 ENTR 00 ENTR to remove DAC commands (zero CHAN 12, BITS 2, 8 and 11, after completion of gimbal drive test.

RECOVERY/ TERMINATION:

- 1. EMP SL-22 is not restart protected. If restart occurs during operation of EMP, redo steps 1, 3, and 4 of PROCEDURES.
- 2. EMP SL-22 is terminated upon completion of the PROCEDURES.

ERASABLE

MEMORY:

NA

UPLINK:

EMP SL-23: MONITOR JET-ON FAILURE

PURPOSE:

EMP SL-23 provides a means of monitoring for jet-on failures and of activating the MASTER ALARM if a failure is detected.

FUNCTIONAL DESCRIPTION:

The DAP attitude errors are monitored once per second. If any error exceeds the DAP deadband (ADB) by more than a specified amount, the ISS warning (Channel 11 Bit 1) is turned on. The ISS warning activates the MASTER ALARM. The erasable cell VHFCNT is zeroed at the start of EMP SL-23 and incremented each pass to provide an indication to the ground that EMP SL-23 is active.

NOTE.—The cell -XDEG (ECADR 644) is to be loaded as the negative of the desired allowable excursion beyond the deadband. It is scaled B-1 rev. The value shown in this document is equivalent to approximately 1 degree.

ASSUMPTIONS:

- Program coding has been uplinked.
- CMC mode is AUTO or HOLD and the CSM-alone DAP or Docked DAP is active.

RESTRICTIONS AND LIMITATIONS:

- If any VERB 37 major mode change or restart has occurred after EMP SL-23 coding is uplinked, ensure that the program code is intact.
- 2. EMP SL-23 operation does not survive a VERB 37 ENTR xx ENTR. It can be reselected (subject to RESTRICTION 1) via VERB 31 ENTR.
- 3. EMP SL-23 uses the same restart group as AVERAGEG and therefore, should not be active during AVERAGEG.
- 4. VHF marks must not be taken (Do not do VERB 87 during P20 options 0 or 4).
- Automatic maneuvers or CDU failures may cause a false indication of a jet-on failure.
- 6. This EMP is ineffectual in detecting +X jet-on failures in the docked configuration.

PROCEDURES:

- 1. The following preliminary procedures should be accomplished before executing EMP SL-23:
 - a. CMC MODE—AUTO
 - b. SC CONT-CMC
 - c. Turn on CSM-alone DAP or Docked DAP
- 2. Key VERB 5 NOUN 26 ENTR and verify that NOUN 26 is valid for EMP SL-23:

R1 00001

R2 00605

R3 00006

- 3. Key VERB 31 ENTR to call EMP SL-23.
- 4. Key VERB 16 NOUN 45 ENTR to verify operation of EMP SL-23:

R1 xxByy where xx should be counting up to indicate EMP SL-23 active.

RECOVERY/ TERMINATION:

- 1. If the MASTER ALARM has been activated by this EMP, reset as follows:
 - a. To reset Channel 11 Bit 1 (ISS Warning), key VERB 25 NOUN 7 ENTR

11 ENTR

1 ENTR

ENTR

b. Clear MASTER ALARM.

NOTE.—Bit 1 of Channel 11 will continually be set by EMP SL-23 as long as the attitude error exceeds the specified amount.

- 2. EMP SL-23 is restart protected.
- 3. EMP SL-23 is terminated by VERB 37 ENTR xx ENTR.
- 4. If it is desired to terminate EMP SL-23 during P20 without interrupting P20 tracking, the recommended procedure is to key

VERB 37 ENTR 30 ENTR VERB 37 ENTR 20 ENTR

| ECADR | Tag | | Code | Octal |
|--|-----------------|----------------------------|--|--|
| 604 605 606 607 610 611 612 613 | JETCHECK | OCT TS TC OCT OCT CA TS | 0 7 VHFCNT PHASCHNG 05015 77777 7 VAC4USE | 00000 30007 54764 05415 05015 77777 30007 54604 |
| 614 | RECHECK | CS | ADB | 41706 |
| 615 | | AD | -XDEG | 60644 |
| 616 | | TS | L | 54001 |
| 617 | XSCHECK | CA | TWO | 35000 |
| 620 | | TS | JETINDEX | 54645 |
| 621 | | INDEX | JETINDEX | 50645 |
| 622 | | CCS | ERRORX | 11620 |
| 623 | | TC | +2 | 00625 |
| 624 | | TC | LOOPEND | 00632 |
| 625 | | AD | L | 60001 |
| 626 | | CCS | A | 10000 |
| 626 627 630 631 | | TC TC TC | DINGDONG LOOPEND LOOPEND | 00640 00632 00632 |
| 632 | LOOPEND | CCS | JETINDEX | 10645 |
| 633 | | TC | XSCHECK | 00620 |
| 634 | NOBELL | INCR | VHFCNT | 24764 |
| 635 | | TC | FIXDELAY | 05270 |
| 636 | | DEC | 100 | 00144 |
| 637 640 641 642 | DINGDONG | TC CAF EXTEND WOR | RECHECK BIT1 DSALMOUT | 00614 35001 00006 05011 |
| 643 | -XDEG | TC | NOBELL | 00634 |
| 644 | | OCT | 77643 | 77643* |
| 645 | JETINDEX | OCT | 0 | 00000 |

^{*}This octal value represents approximately 1 degree.

UPLINK:

Uplink for loading EMP $SL\mbox{-23}$ code by P27 is as follows:

| Load 1 | Load 2 | Load 3 |
|--------|---------|--------|
| V71E | V71E | V71E |
| 24E | 21E | 5E |
| 604E | 626E | 1016E |
| E | 10000E | 1 E |
| 30007E | 640E | 605E |
| 54764E | 632E | 6E |
| 5415E | 632E | V33E |
| 5015E | 10645E | |
| 77777E | 620E | |
| 30007E | 24764E | |
| 54604E | 5270E | |
| 41706E | 144E | |
| 60644E | 614E | |
| 54001E | 35001E | |
| 35000E | 6E | |
| 54645E | 5011E | |
| 50645E | 634E | |
| 11620E | *77643E | |
| 625E | V33E | |
| 632E | | |
| 60001E | | |
| V33E | | |
| | | |

 $^{^{*}}$ This octal value represents approximately 1 degree.

EMP SL-26: IMU CDU TRANSIENT MONITOR

PURPOSE:

EMP SL-26 provides a means of restoring a CDU counter and of activating the MASTER ALARM and OPR ERR when a CDU transient has occurred. This EMP is not intended to operate during the Rendezvous phase of the mission.

FUNCTIONAL DESCRIPTION:

Each CDU angle from 0.1 second previous is subtracted from its present value. If the magnitude of the result is greater than a specified amount, * the previous value is stored into the CDU counter and channel 11 is set as follows:

bit 01 = 1 ISS WARNING

bit 07 = 1 OPR ERR

bit 11 = 1 if CDUX transient

bit 12 = 1 if CDUY transient

bit 15 = 1 if CDUZ transient

CDUZ, CDUY and CDUX are checked, in that order. EMP SL-26 was designed to prevent COARSE ALIGN with actual yaw angles of 60 deg. or less, when a CDUZ transient occurs.

EMP SL-26 is initialized and enabled by VERB 31 ENTR and is connected to the downlink interrupt processing program by loading the register DNTMGOTO with the starting location of EMP SL-26. Since operation of this EMP is controlled by the downlink interrupt, a major mode change will not deactivate it (except as described in RECOVERY/TERMINATION).

This EMP also increments the register VHFCNT every 0.1 second. Noun 45 can be displayed to confirm that the EMP is operating. (R1 is incrementing.)

The register -NDEGS (ECADR 2511) is to be loaded as the negative of the desired CDU change threshold. It is scaled B-1 rev. The value shown in this EMP is equivalent to approximately 4 degrees.

Since EMP SL-26 is also operated by EMP SL-28, the OPR ERR light is lit in addition to the MASTER ALARM to distinguish a CDU transient from a jet-on failure. A jet-on failure, detected by EMP SL-28, will only turn on the MASTER ALARM.

ASSUMPTIONS:

- 1. Program coding has been uplinked
- 2. Downlink interrupts are received every 20 ms (high bit rate) or every 100 ms (low bit rate).
- 3. The W-matrix is invalid and will not be integrated.

RESTRICTIONS

AND LIMITATIONS:

- 1. MINKEY, P20, options 0 and 4, P31, P32, P33, P34, P35, P36 or self-check are not operating.
- VERB 74 ENTR or VERB 36 ENTR terminate this EMP. However, if a hardware restart (or VERB 69 ENTR) occurs after VERB 74 ENTR and before any VERB 37 ENTR xx ENTR the EMP will be restarted.
- 3. Gimbal angle errors as great as twice the magnitude of the angle chosen may result if a transient occurs.
- 4. This EMP is not restart protected during P11, in the interval TIG -5 to ignition and in P40 from engine cut-off -6 to cut-off. A hardware restart (or VERB 69 ENTR) at these times will terminate this EMP.
- 5. It is possible for large attitude rates to induce gimbal angle rates that would cause erroneous detection of a CDU transient, effectively freezing that CDU and resulting in loss of attitude control in that axis.

In selecting the value of -NDEGS the following table, showing the relationship of gimbal angle rates to body rate for various middle gimbal angles, should be consulted.

| -NDEGS | Max GA Rate | Maximum Allowable Body Rate in Deg/Sec | | | | |
|--------|-------------|--|----------|----------|----------|----------|
| deg | deg/sec | MGA = 10 | MGA = 20 | MGA = 30 | MGA = 45 | MGA = 60 |
| 1 | 10 | 8 | 6.6 | 5.5 | 4.1 | 2.9 |
| 2 | 20 | 16 | 13.2 | 11 | 8.3 | 5.8 |
| 3 | 30 | 24 | 19.8 | 16.5 | 12.9 | 8.7 |
| 4 | 40 | 32 | 26.4 | 22 | 16.6 | 11.6 |

PROCEDURES:

1. Key VERB 5 NOUN 26 ENTR and verify that N26 is valid for EMP SL-26.

R1 00001

R2 01517

R3 00005

- 2. Key VERB 31 ENTR to start EMP SL-26.
- 3. Key VERB 16 NOUN 45 ENTR to verify operation of EMP SL-26.

R1 XXBYY

where XX should be counting up to indicate EMP SL-26 is active.

RECOVERY/ TERMINATION:

 If the MASTER ALARM has been activated by this EMP, no program alarm will appear. Channel 11 indicates which CDU was affected. To determine which CDU was affected, key —

VERB 1 NOUN 10 ENTR

11 ENTR

Interpret R1 as follows:

4XXXX - CDUZ

5XXXX - CDUZ

X4XXX - CDUY

X5XXX - CDUY

X2XXX - CDUX X3XXX - CDUX

X6XXX - CDUX and CDUY X7XXX - CDUX and CDUY

To reset OPR ERR, Channel 11 and ISS WARNING, key—
RSET
VERB 25 NOUN 7 ENTR
11 ENTR
46001 ENTR
ENTR
Reset MASTER ALARM

If OPR ERR cannot be cleared by RSET, a CDU runaway is in progress. The MASTER ALARM light can be shut off even though the alarm condition still exists but the OPR ERR light cannot.

- 2. If the MASTER ALARM has been activated by this EMP, IMU CDU ZERO should be performed as soon as possible to synchronize CDU counters. This EMP does not have to be disabled to perform IMU CDU ZERO (VERB 40 ENTR).
- 3. EMP SL-26 is terminated by restoring register DNTMGOTO with the downlink location and disengaging restart protection. This may be done in the following ways:
 - a. VERB 74 ENTR followed by:VERB 37 ENTR xx ENTR.(No wait required after VERB 74 ENTR.)
 - b. VERB 36 ENTR
 - c. VERB 21 NOUN 1 ENTR
 334 ENTR
 3454 ENTR,
 followed by VERB 37 ENTR xx ENTR.
- 4. If it is desired to resume EMP SL-26 after it is terminated repeat PROCEDURES.

ERASABLE MEMORY:

Program coding for EMP SL-26 is as follows: Initialization portion of EMP SL-26:

| ECADR | Tag | | Code | Octal |
|-------|----------|--------|----------|--------|
| 2400 | STARTV31 | EXTEND | | 00006 |
| 2401 | | DCA | CDUX | 30033 |
| 2402 | | DXCH | XSAVE | 53513 |
| 2403 | | CA | CDUZ | 30034 |
| 2404 | | TS | XSAVE +2 | 55514 |
| 2405 | | CA | ZERO | 35003 |
| 2406 | | TS | 528CTR | 55370 |
| 2407 | | CA | TIME1 | 30025 |
| 2410 | | TS | TIME.R | 55516 |
| 2411 | | CA | STARTLOC | 31414 |
| 2412 | | TS | DNTMGOTO | 54334 |
| 2413 | | TC | TASKOVER | 05327 |
| 2414 | STARTLOC | ADRES | START526 | 01372 |
| | | | | |
| 2517 | | TC | STARTV31 | 01400* |
| | | | | |

 $^{^{*}}$ This location is modifed by EMP SL-28.

DOWNLINK operated portion of EMP SL-26:

| ECADR | Tag | | Code | Octal |
|--|-----------------|---|--|--|
| 1372 1373 1374 | START526 | CA TS TC | EBANK5 EBANK START | 35055 54003 01415 |
| 2415 2416 2417 2420 2421 2422 2423 | START | CCS TC TC OCT OCT 2CADR | PHASE3 +6 PHASCHNG 07013 77777 STARTV31 | 11152 01424 05415 07013 77777 01400 00005 |
| 2423 2424 2425 2426 2427 2430 2431 2432 2433 2434 2435 2436 2437 2444 2444 2444 2444 2444 2444 2445 2444 2445 2446 2451 2451 2451 2451 2451 2451 2451 2451 | CHK CDU LOOP | CS AD CCS COM AD AD AD CCS TC TC TC TC CAF TS CA MASK CCS TC INDEX CA EXTEND INDEX MSU CCS TC TC AD CCS | TIME1 TIME.R A OCT37776 ONE -0.1SEC A CHKCDU CHKCDU DNPHASE2 TWO IX IMODES33 BIT6 A OK IX CDUX IX XSAVE A +2 OK -NDEGS A | 40005 40025 61516 10000 40000 67663 65001 61510 10000 01437 03452 35000 55515 31324 74774 10000 01462 51515 20006 51515 21512 10000 01455 01462 61511 10000 |
| 2457 2460 2461 2462 2463 2464 2465 | OK | TC TC TC INDEX CA INDEX TS | BELLS OK OK IX CDUX IX XSAVE | 01475 01462 01462 51515 30032 51515 |
| 2466 2467 2470 2471 2472 2473 | LOOP/CON | CCS TC CA TS INCR INCR | IX LOOP TIME1 TIME.R VHFCNT 528CTR | 55512 11515 01440 30025 55516 24764 25370 |
| 2474 2475 2476 | BELLS | TC INDEX CA | FIXRSTRT IX ALARMX | 01525 51515 31505 |

| 2477 2500 2501 2502 2503 2504 2505 2506 2507 2510 2511 2512 | ALARMX -0.1SEC -NDEGS XSAVE IX | TC INDEX CA INDEX TS TC OCT OCT OCT OCT OCT OCT | FALTON +1 IX XSAVE IX CDUX LOOP/CON 02101 04101 40101 77765 77224 | 04363 51515 31512 51515 54032 01466 02101 04101 40101 77765 77224* |
|--|--------------------------------|---|---|--|
| 2516 2525 2526 | TIME.R FIXRSTRT | CA TS | NEGO PHSPRDT3 | 35002 55254 |
| 2527 | | TC | DNPHASE2 | 03452 |

77644=1 degree 77511=2 degrees 77356=3 degrees

 $^{^{*}}$ The value shown is approximately 4 degrees. Other values are:

UPLINK: Uplink for loading EMP SL-26 code by P27 is as follows:

| Load 1 | Load 2 | Load 3 | Load 4 | Load 5 | Load 6 |
|--------|-------------------|--------|--------|---------|--------|
| V71E | V71E | V71E | V71E | V72E | V71E |
| 24E | 24E | 24E | 24E | 23E | 5 E |
| 2400E | 2422E | 2444E | 2466E | 2511E | 2525E |
| 6E | 1400E | 1462E | 11515E | *77224E | 35002E |
| 30033E | 5 E | 51515E | 1440E | 1372E | 55254E |
| 53513E | 40025E | 30032E | 30025E | 35055E | 3452E |
| 30034E | 61516E | 6E | 55516E | 1373E | V33E |
| 55514E | 10000E | 51515E | 24764E | 54003E | |
| 35003E | 40000E | 21512E | 25370E | 1374E | |
| 55370E | 67663E | 10000E | 1525E | 1415E | |
| 30025E | 65001E | 1455E | 51515E | 1016E | |
| 55516E | 61510E | 1462E | 31505E | 1E | |
| 31414E | 10000E | 61511E | 4363E | 1017E | |
| 54334E | 1437E | 10000E | 51515E | 1517E | |
| 5327E | 1437E | 1475E | 31512E | 1020E | |
| 1372E | 3452E | 1462E | 51515E | 5E | |
| 11152E | 35000E | 1462E | 54032E | 2510E | |
| 1424E | 55515E | 51515E | 1466E | 77765E | |
| 5415E | 31324E | 30032E | 2101E | 2517E | |
| 7013E | $74774\mathrm{E}$ | 51515E | 4101E | 1400E | |
| 77777E | 10000E | 55512E | 40101E | V33E | |
| V33E | V33E | V33E | V33E | | |
| | | | | | |

77224E for 4 degree check 77356E for 3 degree check 77511E for 2 degree check 77644E for 1 degree check

^{*} Load:

EMP SL-27: MONITOR SINGLE IMU CDU

PURPOSE:

EMP SL-27 provides a means of restoring a particular IMU CDU counter and of activating the MASTER ALARM and OPR ERR when a CDU transient has occurred in the particular CDU. This EMP is intended for use during terminal phase rendezvous.

FUNCTIONAL DESCRIPTION:

The designated CDU angle from 0.24 second previous (high bit rate) or 0.2 second (low bit rate) previous is subtracted from its present value. If the magnitude of the result is greater than 4 degrees, the previous value is stored into the CDU counter and channel 11 is set as follows:

bit 1 = 1, ISS WARNING bit 7 = 1, OPR ERR

If CDUZ is checked, EMP SL-27 will prevent COARSE ALIGN with actual yaw angles of 60 deg. or less, when a transient occurs.

EMP SL-27 is initialized and enabled by VERB 31 ENTR and is connected to the downlink interrupt processing program by loading the register DNTMGOTO with the starting location of EMP SL-27. Since operation of this EMP is controlled by the downlink interrupt, a major mode change will not deactivate it.

ASSUMPTIONS:

- 1. Program coding has been uplinked.
- 2. Downlink interrupts are received every 20 ms (high bit rate) or every 100 ms (low bit rate).

NOTE.—See Step 3 of PROCEDURES.

RESTRICTIONS
AND LIMITATIONS:

- 1. P31, P32, P33, P34 and self-check are not operating.
- 2. EMP SL-27 is not restart protected.
- 3. A hardware restart, VERB 69 ENTR, VERB 74 ENTR, or VERB 36 ENTR terminates EMP SL-27.

- 4. Gimbal angle errors as great as 8 degrees may result if a transient occurs.
- 5. Because this EMP operates from the telemetry interrupt, consideration must be given to the technique of switching bit rates in the CSM.

When the CSM telemetry bit rate and the EMP are compatible, it is looking for an equivalent CDU rate of greater than 16.8 degrees/second during high bit rate and 20 degrees/second during low bit rate.

When the CSM is in low bit rate but the EMP is set for high bit rate, then it is looking for an equivalent CDU rate of 3.3 degrees/second; adequate for transient detection, but close to realistic CDU rates which could unnecessarily trip the alarm.

When the CSM is in high bit rate but the EMP is set for low bit rate, then it is looking for an equivalent CDU rate of 100 degrees/second, effectively disabling the transient detection.

If continuous transient detection is essential, then when going from high to low bit rate location 1366 should be changed after the switch is thrown. Conversely when going from low to high bit rate location 1366 should be changed before the switch is thrown.

If continuous transient detection is not essential it is probably easier to always modify location 1366 after throwing the switch.

6. It is possible for large attitude rates to induce gimbal angle rates that would cause erroneous detection of a CDU transient, effectively freezing that CDU and resulting in lose of attitude control in that axis. Maximum allowable body rates are:

for

10 deg MGA = 13.33 deg/sec 20 deg MGA = 11.00 deg/sec 30 deg MGA = 9.17 deg/sec 45 deg MGA = 6.83 deg/sec 60 deg MGA = 4.83 deg/sec

PROCEDURES:

1. Key VERB 5 NOUN 26 ENTR and verify that N26 is valid for EMP SL-27.

R1 00001 R2 01440 R3 00004

- 2. Key VERB 31 ENTR to start EMP SL-27.
- 3. If it is desired to switch between high and low telemetry rates, location 1366 can be loaded by VERB 21 NOUN 1 ENTR 1366 ENTR xx ENTR

where xx is 01 - low bit rate where xx is 13 - high bit rate

RECOVERY/ TERMINATION:

 If the MASTER ALARM has been activated by this EMP, no program alarm will appear.

To reset Channel 11, OPR ERR and ISS WARNING,

key

RSET

VERB 25 NOUN 7 ENTR

11 ENTR

1 ENTR

ENTR

Reset MASTER ALARM

If OPR ERR cannot be cleared by RSET a CDU runaway is in progress. The MASTER ALARM light can be shut off even though the alarm condition still exists but the OPR ERR light can not.

- 2. If the MASTER ALARM has been activated by this EMP, IMU CDU ZERO should be performed as soon as possible to synchronize CDU counters. The EMP does not have to be disabled to perform IMU CDU ZERO (VERB 40 ENTR).
- 3. EMP SL-27 is not restart protected.
- 4. EMP SL-27 is terminated by a hardware restart, VERB 36 ENTR, VERB 69 ENTR or VERB 74 ENTR.
- 5. If it is desired to resume EMP SL-27 after it is terminated, repeat PROCEDURES.

ERASABLE MEMORY:

Program coding for EMP SL-27 is as follows: Initialization portion of EMP SL-27:

| ECADR | Tag | - <u>C</u> | Code | Octal |
|--|------------------------------|--------------------------------------|---|--|
| 2040 2041 2042 2043 2044 2045 2046 2047 2050 2051 2052 | S27LOC CONT1X | CA TS CA TS CA TS TC ADRES CCS TC TC | CDU? CDUSAVE OCT13E COUNTER S27LOC DNTMGOTO TASKOVER START A INV40 CONT2X | 3003X* 55367 31366 55370 31447 54334 05327 01372 10000 01775 01375 |
| | Downlink o | perated por | tion of EMP SI | J-27: |
| 1366 1367 1370 | OCT13E CDUSAVE COUNTER | OCT OCT OCT | 00013 00000 00000 | 00013** 00000 00000 |
| 1372 1373 1374 1375 1376 1377 | START CONT2X | CA TS TC CA TS | EBANK 4 EBANK S27GO EBANK 5 EBANK CONT3X | 34767 54003 01757 35055 54003 01444 |
| 2357 2360 2361 2362 2363 2364 2365 2366 2367 2370 | S27GO OUTX CHKCDU | CCS TC CA TC TS TC TS CA MASK TC | COUNTER OUTX OCT13E CHKCDU COUNTER DNPHASE2 COUNTER IMODES33 BIT6 CONT1X | 11370 01763 31366 01765 55370 03452 55370 31324 74774 01450 |
| 2375 2376 2377 | INV40 | CA TS TC | CDU? CDUSAVE DNPHASE2 | 3003X* 55367 03452 |
| 2444 2445 2446 2447 2450 2451 | CONT3X | CA EXTEND MSU CCS TC | CDU? CDUSAVE A +2 OK | 3003X* 00006 21367 10000 01452 01457 |

| 2452 | | AD | -NDEGS | 61537 |
|------|--------|-----|-----------|--------|
| 2453 | | CCS | A | 10000 |
| 2454 | | TC | BELLS | 01532 |
| 2455 | | TC | OK | 01457 |
| 2456 | | TC | OK | 01457 |
| 2457 | OK | CA | CDU? | 3003X* |
| 2460 | | TS | CDUSAVE | 55367 |
| 2461 | | TC | DNPHASE2 | 03452 |
| | | | | |
| 2532 | BELLS | CA | ALARMX | 31540 |
| 2533 | | TC | FALTON +1 | 04363 |
| 2534 | | CA | CDUSAVE | 31367 |
| 2535 | | TS | CDU? | 5403X* |
| 2536 | | TC | DNPHASE2 | 03452 |
| 2537 | -NDEGS | OCT | 77224 | 77224 |
| 2540 | | OCT | 00101 | 00101 |
| | | | | |

X = 2, CDUX monitor
X = 3, CDUY monitor
X = 4, CDUZ monitor

00013 - high bit rate 00001 - low bit rate

^{*}These locations must be changed to select the IMU CDU to be monitored.

^{**}EMP SL-27 operates from the telemetry interrupt, location 1366 should be loaded as follows: (See RESTRICTIONS & LIMITATIONS paragraph 5)

Uplink for loading EMP SL-27 code by P27 is as follows:

UPLINK:

| Load 1 | Load 2 | Load 3 | Load 4 | Load 5 | Load 6 |
|---------|--------|--------|---------|---------|---------|
| | | | | | |
| V71E | V71E | V71E | V71E | V71E | V72E |
| 15E | 14E | 14E | 20E | 11E | 15E |
| 2040E | 1366E | 2357E | 2444E | 2532E | 1016E |
| *3003XE | **13E | 11370E | *3003XE | 31540E | 1 E |
| 55367E | E | 1763E | 6E | 4363E | 1017E |
| 31366E | E | 31366E | 21367E | 31367E | 1440E |
| 55370E | E | 1765E | 10000E | *5403XE | 1020E |
| 31447E | 34767E | 55370E | 1452E | 3452E | 4E |
| 54334E | 54003E | 3452E | 1457E | 77224E | 2375E |
| 5327E | 1757E | 55370E | 61537E | 101E | *3003XE |
| 1372E | 35055E | 31324E | 10000E | V33E | 2376E |
| 10000E | 54003E | 74774E | 1532E | | 55367E |
| 1775E | 1444E | 1450E | 1457E | | 2377E |
| 1375E | V33E | V33E | 1457E | | 3452E |
| V33E | | | *3003XE | | V33E |
| | | | 55367E | | |
| | | | 3452E | | |
| | | | V33E | | |

00013 - high bit rate 00001 - low bit rate

^{*}These locations must be changed to select the IMU CDU to be monitored.

X = 2, CDUX monitor
X = 3, CDUY monitor
X = 4, CDUZ monitor

^{**}EMP SL-27 operates from the telemetry interrupt, location 1366 should be loaded as follows: (See RESTRICTIONS & LIMITATIONS paragraph 5)

EMP SL-28: MONITOR JET-ON FAILURE AND DO EMP SL-26

PURPOSE:

EMP SL-28 provides a means of monitoring for jet-on failures and of activating the MASTER ALARM if a failure is detected. EMP SL-28 also operates EMP SL-26 (IMU CDU TRANSIENT MONITOR) and is intended as a replacement for EMP SL-23 when both jet-on failure detection and CDU transient monitoring are desired.

FUNCTIONAL DESCRIPTION:

The DAP attitude errors are monitored once every second. If any error exceeds the DAP deadband (ADB) by more than a specified amount, the ISS WARNING (Channel 11 Bit 1) is turned on. The ISS WARNING activates the MASTER ALARM. EMP SL-28 is initialized and enabled by VERB 31 ENTR and is connected to the downlink interrupt processing program by loading DNTMGOTO with the starting address of EMP SL-28. Since operation of this EMP is controlled by the downlink interrupt, a major mode change will not deactivate it (except as described in RECOVERY/TERMINATION).

EMP SL-28 also initializes and operates EMP SL-26 which samples the CDU's every .1 second and turns on the MASTER ALARM plus the OPR ERR light if a CDU change exceeds a specified amount. For details see EMP SL-26.

Provided that the CDU transient threshold angle (register -NDEGS in EMP SL-26) is set greater than 1.5 degrees (equivalent rate greater than 15 degrees per second), most failures should be distinguishable from CDU transients.

For a 35,000 lb. vehicle, assuming that jets A3, C4, B3, D4, A1, and C2 (or D1, B2) are the only ones enabled, a worst case (roll) jet-on failure can introduce an attitude rate greater than 10 degrees per second after 5 seconds from the failure, greater than 20 degrees per second after 25 seconds from the failure, and continuing to increase thereafter. If the jet-fail condition is not corrected before the specified CDU change threshold (register -NDEGS in EMP SL-26) is exceeded, a CDU transient will be erroneously detected, the OPR ERR turned on, and the CDU

essentially frozen. With a frozen CDU the autopilot becomes ineffective in counteracting the failed-on jet. Jet-on failures in the pitch and yaw axes introduce attitude rates of about 1/3 those of the roll axis.

NOTE.—The cell -XDEG (ECADR 647) is to be loaded as the negative of the desired allowable excursion beyond the deadband for jet-on failure monitoring. It is scaled B-1 rev. The value shown in this document is equivalent to approximately 1 degree.

ASSUMPTIONS:

- 1. Program coding has been uplinked.
- 2. EMP SL-26 has been uplinked. See EMP SL-26.
- CMC mode is AUTO or HOLD and the RCS DAP is active.
- 4. Downlink interrupts are received every 20 ms (high bit rate) or every 100 ms (low bit rate).
- 5. The W-matrix is invalid and will not be integrated.

RESTRICTIONS AND LIMITATIONS:

- 1. This EMP is intended and verified for use only in P00 and P20 options 2 and 5.
- 2. If a VERB 37 major mode change or a restart occurs following the uplink of EMP SL-28 coding and before VERB 31 ENTR, VAC area 4 should be checked to ensure that the program code is intact.
- 3. The RESTRICTIONS and LIMITATIONS of EMP SL-26 apply.
- 4. Automatic maneuvers may cause a false indication of a jet-on failure.
- 5. This EMP is ineffectual in detecting +X jet-on failures in the docked configuration.

PROCEDURES:

- 1. The following preliminary procedures should be accomplished before executing EMP SL-28:
 - a. CMC MODE-AUTO or HOLD
 - b. SC CONT—CMC
 - c. Turn on RCS DAP

2. Key VERB 5 NOUN 26 ENTR and verify that NOUN 26 is valid for EMP SL-28:

> R1 00001 R2 01522 R3 00005

3. Key VERB 31 ENTR to call EMP SL-28.

RECOVERY/ TERMINATION:

1. If the MASTER ALARM has been activated by this EMP, and OPR ERR light is not on, a jet-on failure was detected. If OPR ERR light also is on, a CDU transient was detected and Channel 11 indicates which CDU was affected. To display contents of Channel 11, key—

VERB 1 NOUN 10 ENTR 11 ENTR

Interpret R1 as follows:

4XXXX—CDUZ

5XXXX—CDUZ

X4XXX—CDUY

X5XXX—CDUY

X2XXX—CDUX

X3XXX—CDUX

X6XXX-CDUX and CDUY

X7XXX-CDUX and CDUY

To reset OPR ERR, Channel 11 and MASTER ALARM,

key

RSET

VERB 25 NOUN 7 ENTR

11 ENTR

46001 ENTR

ENTR

Reset MASTER ALARM.

NOTE.—Bit 1 of Channel 11 will continually be set as long as the DAP attitude error exceeds the specified amount.

Bits 1 and 7 (OPR ERR) of Channel 11 will continually be set as long as a CDU transient is present. If OPR ERR cannot be cleared by RSET, a CDU runaway is in progress. The MASTER ALARM light can be shut off even though the alarm condition still exists, but the OPR ERR light can not.

If a CDU transient occurred IMU CDU ZERO (VERB 40 ENTR) should be performed as soon as possible to synchronize CDU counters. A false indication of jet-on failure may be detected in the interval before the CDU ZERO.

- 2. EMP SL-28 is terminated by restoring register DNTMGOTO to the downlink location and disengaging restart protection. This may be done in the following ways.
 - a. VERB 74 ENTR followed by:

 VERB 37 ENTR XX ENTR (No wait required after VERB 74 ENTR.)
 - b. VERB 36 ENTR
 - c. VERB 21 NOUN 1 ENTR
 334 ENTR
 3454 ENTR
 followed by VERB 37 ENTR xx ENTR
- 3. EMP SL-28 may be terminated and EMP SL-26 continued by executing EMP SL-26 PROCEDURES.

ERASABLE MEMORY:

Program coding for EMP SL-28 is as follows:

| | 9 | | | |
|---|-----------------------------|--|--|--|
| ECADR | Tag | | Code | Octal |
| 604 605 606 607 610 611 612 | 528START | OCT CS AD CCS TC TC TC | 00000 528CTR TEN A NOBELL +2 +1 | 00000 41370 64355 10000 00635 00613 |
| 613 614 615 616 617 620 | | TS TC CS AD TS CA | 528CTR E6SETTER ADB -XDEG L TWO | 55370 04611 41706 60647 54001 35000 |
| 621 622 623 624 625 | XSCHECK | TS INDEX CCS TC TC | JETINDEX JETINDEX ERRORX +2 LOOPEND | 54646 50646 11620 00626 00633 |
| 626 627 630 631 632 | | AD CCS TC TC TC | L A DINGDONG LOOPEND LOOPEND | 60001 10000 00642 00633 00633 |
| 633 634 | LOOPEND | CCS TC | JETINDEX XSCHECK | 10646 00621 |
| 635 636 637 640 641 | NOBELL | CA TS CA TS TC | EBANK5 EBANK ZERO VAC4USE START* | 35055 54003 35003 54604 01415 |
| 642 643 644 | DINGDONG | CAF TC TC | BIT1 FALTON+1 NOBELL | 35001 04363 00635 |
| 645 646 647 | 528LOC JETINDEX -XDEG | ADRES OCT OCT | 528START 00000 77643** | 00605 00000 77643 |
| 2517 2520 2521 2522 2523 2524 | 526LOC | CA TS TC CA TC ADRES | 526LOC STARTLOC* STARTV31* 528LOC -3 START526 | 31524 55414 01400 30645 01520 01372 |
| | 528CTR | 1101(110 | 2221(1000 | 01012 |
| 1370 | J20C1R | | | |

^{*} These locations are in EMP SL-26.

 $^{^{**}}$ This register specifies the allowable excursion beyond the deadband. The value shown is approximately 1 degree.

Uplink for loading EMP SL-28 code by P27 is as follows:

UPLINK:

| Load 1 | Load 2 | Load 3 |
|--------------|---------|--------|
| V71E | V71E | V72E |
| 24E | 24E | 23E |
| 604E | 626E | 2517E |
| \mathbf{E} | 60001E | 31524E |
| 41370E | 10000E | 2520E |
| 64355E | 642E | 55414E |
| 10000E | 633E | 2521E |
| 635E | 633E | 1400E |
| 613E | 10646E | 2522E |
| 613E | 621E | 30645E |
| 55370E | 35055E | 2523E |
| 4611E | 54003E | 1520E |
| 41706E | 35003E | 2524E |
| 60647E | 54604E | 1372E |
| 54001E | 1415E | 1016E |
| 35000E | 35001E | 1 E |
| 54646E | 4363E | 1017E |
| 50646E | 635E | 1522E |
| 11620E | 605E | 1020E |
| 626E | E | 5 E |
| 633E | *77643E | V33E |
| V33E | V33E | |

 $^{^{\}ast}$ This register may be modified to select any desired excursion beyond the deadband. The value shown is approximately 1 degree.

EMP SL-50: CONVERT GYRO TORQUING ANGLES TO CDU ANGLES FOR FAILED IMU

PURPOSE:

EMP SL-50 provides a means of converting the gyrotorquing angles calculated by P52 into the resultant actual CDU angles, and of updating NOUN 20 with the CDU angles if desired. The NOUN 20 angles may then be used to do GDC Realign.

FUNCTIONAL DESCRIPTION:

Normally, P52 calculates the gyro-torquing angles necessary to torque the stable member into agreement with REFSMMAT, and performs the torquing as specified in NOUN 93. If the IMU has failed, this EMP uses the input to the calculation of the NOUN 93 angles to compute CDU angles, displays them, and, if approved, updates NOUN 20 with them. Since REFSMMAT is not changed and the IMU is unavailable, this EMP effectively makes NOUN 20 reflect the instantaneous relationship between vehicle attitude and a fictitious stable member described by REFSMMAT.

ASSUMPTIONS:

- 1. IMU is unavailable
- 2. A valid REFSMMAT is stored.
- 3. Program coding has been uplinked (see Restriction 1).

RESTRICTIONS AND LIMITATIONS:

- RCS DAP is unavailable. Do VERB 48 ENTR. At FL VERB 04 NOUN 46, key VERB 21 ENTR 0xxxx ENTR. Subsequently, key VERB 46 ENTR. This must be done before EMP SL-50 is uplinked.
- No active extended verbs are permitted between FL VERB 06 NOUN 93 and keying VERB 30 ENTR.
- 3. The EMP requires that the contents of NOUN 20 at the first mark, at the second mark, and at the execution of the EMP (at VERB 30 ENTR) be consistent, even if incorrect. Therfore, it is necessary to load NOUN 20 with the FDAI attitude just prior to the first mark. Thereafter, if the vehicle is maneuvered for the second mark, the FDAI attitude must again be loaded, and, if the vehicle is maneuvered prior to the execution of the EMP, the FDAI attitude must be loaded once again.

4. The gimbal angles calculated are correct for the time the EMP is executed. Constant FDAI attitude must therefore be maintained from that time until GDC Align.

PROCEDURES:

1. If REFSMFLG (FLAGWRD3, bit 13) is not set, key:

VERB 25 NOUN 07 ENTR

77 ENTR

10000 ENTR

1 ENTR, to set REFSMFLG and allow P52

2. Verify NOUN 46 R1=0xxxx.

If R1 is not 0xxxx, program coding must be reloaded.

3. Key VERB 05 NOUN 26 ENTR to verify that NOUN 26 contains:

R1 10001

R2 01642

R3 50006

- 4. Key VERB 37 ENTR 52 ENTR to begin P52, option 3. Follow option 3 procedures until the appearance of FL VERB 51 for the first mark.
- At FL VERB 51 for the first mark, maneuver, if necessary, to acquire the first mark body.

Key-

VERB 25 NOUN 20 ENTR

and load the FDAI bail angles into NOUN 20. Perform the mark, and follow option 3 procedures until FL VERB 51 for the second mark.

- 6. At FL VERB 51 for the second mark, if the vehicle has been maneuvered since NOUN 20 was loaded for the first mark, the new FDAI attitude must be loaded via VERB 25 NOUN 20 before the second mark is taken.
- 7. After the second mark has been taken, follow option 3 procedures until the appearance of FL VERB 06 NOUN 93.
- 8. At FL VERB 06 NOUN 93, if the vehicle has been maneuvered since the second mark, the new FDAI attitude must be loaded via VERB 25 NOUN 20 before continuing into the EMP.
- 9. After loading NOUN 20 (if necessary), verify that no active extended verbs exist.

Key-VERB 30 ENTR To start EMP SL-50.

- 10. Observe FL VERB 06 NOUN 22, containing the CDU angles which relate vehicle attitude to REFSMMAT. If they are acceptable, key PRO to transfer the CDU angles to NOUN 20. Otherwise, key VERB 34 ENTR to exit EMP.
- 11. At reappearance of NOUN 93, key VERB 32 ENTR.
- 12. At FL VERB 50 NOUN 25, R1 00014, the normal options exist.
- 13. The gimbal angles calculated are correct for the time the EMP is executed. Constant FDAI attitude must therefore be maintained from that time until GDC align.

RECOVERY/ TERMINATION:

EMP SL-50 is not separately restart protected; normal P52 recovery procedures apply. After keying VERB 30 ENTR, a restart will cause the appearance of FL VERB 01 NOUN 70 for the second mark, and these procedures may be resumed at that point.

ERASABLE MEMORY:

Program coding for EMP SL-50 is as follows:

| ECADR | Tag | Code | | Octal |
|--|---------------------|--|---|---|
| 1016 1017 1020 | N26/PRI N26/2CAD | OCT OCT OCT | 10001 01642 50006 | 10001 01642 50006 |
| 3242 3243 3244 3245 3246 3247 3250 3251 3252 3253 3254 3255 3256 3257 3260 3261 3262 | START | TC VLOAD STORE VLOAD STORE VLOAD STORE RTB CADR RTB | INTPRET XDC XSM YDC YSM ZDC ZSM E/CALL CDUTRIG E/CALL CALCSMSC | 06006 77775 02703 02661 77775 02711 02667 77775 02717 02675 77634 24017 47471 77634 24017 34747 77634 |
| 3263 3264 3265 3266 3267 3270 3271 3272 3273 3274 3275 3276 3277 3300 3301 3302 3303 3304 3305 | CDUSTOR | CADR EXIT CA TS CA TC CADR CADR TC TC TC INHINT EXTEND DCA DXCH CA TS TC | E/CALL CALCGA OCT24 EXTVBACT V06N22 BANKCALL E/BKCALL GOMARK F ENDMARK CDUSTOR ENDMARK THETAD CDUX THETAD CDUX THETAD+2 CDUZ ENDMARK | 24017 47303 77776 34124 55237 35040 04647 24000 20456 05537 01677 05537 00004 00006 31300 52033 31301 54034 05537 |

UPLINK:

P27 uplink for EMP SL-50 is as follows:

| Load 1 | Load 2 | Load 3 |
|--------|--------|--------|
| V71E | V71E | V71E |
| 5 E | 24E | 24E |
| 1016E | 3242E | 3264E |
| 10001E | 6006E | 47303E |
| 1642E | 77775E | 77776E |
| 50006E | 2703E | 34124E |
| V33E | 2661E | 55237E |
| | 77775E | 35040E |
| | 2711E | 4647E |
| | 2667E | 24000E |
| | 77775E | 20456E |
| | 2717E | 5537E |
| | 2675E | 1677E |
| | 77634E | 5537E |
| | 24017E | 4E |
| | 47471E | 6E |
| | 77634E | 31300E |
| | 24017E | 52033E |
| | 34747E | 31301E |
| | 77634E | 54034E |
| | 24017E | 5537E |
| | V33E | V33E |
| | | |

EMP SL-51 GENERALIZED ROTATIONAL RATE GENERATOR

PURPOSE:

This EMP provides a means of imparting a rotational rate to the Orbital Assembly. This capability can be of use in conjunction with docked +X translation maneuvers, CMG desaturation and the initiation of "Wide Deadband Attitude Hold".

During a docked RCS translational maneuver in the FREE mode, the +X jets do not thrust through the vehicle center of gravity (c.g.); a body attitude rate disturbance will therefore be imparted to the vehicle. In order to counter this body rate and also leave the contaminants from the attitude control firing jets in the old orbit, this EMP will generate opposing body rates prior to the translational maneuver.

CMG desaturation essentially involves changing the momentum state of the CMGs by a specified amount. One way of doing this is by using the RCS jets to apply an impulse to the OA which, when counteracted by the CMGs, will drive the CMGs to the desired final state. The angular rate commands needed to produce the proper impulse can be computed in advance external to the CMC.

Generally, at the initiation of the Wide Deadband Mode, the optimum vehicle rate is non-zero. EMP SL-51 can be used to impart the optimum rates to the vehicle at the initiation of the Wide Deadband Mode.

The EMP also has an option for restoring the DAP to its conventional attitude hold status after the EMP has been used in conjunction with any of the three above stated activities.

FUNCTIONAL DESCRIPTION:

Figure 1 is a functional flow graph of EMP SL-51. This EMP has two entry points for use in initiating rates. One entry point is used when rates are being imparted to the vehicle in conjunction with +X translations or CMG desaturation. The second entry point is for the initiation of the Wide Deadband Mode. EMP SL-51 also has a third entry point which is used for the restoration option of the EMP.




FIGURE SL-51-1: FUNCTIONAL FLOW DIAGRAM.




FIGURE SL-51-1 (continued)

When the +X translation/CMG desaturation entry point is used, EMP SL-51 alters two phase plane parameters to preclude multiple sets of firings. It then loads the desired rates for roll, pitch, and yaw (precomputed by the ground or the crew - one or more of the desired rates can be zero) into double precision DAP cells WBODY, WBODY1, and WBODY2. Finally, it sets HOLDFLAG negative and configures CH31TEMP so that on the next DAP pass, a single set of forced firings will occur that will establish the desired rates.

When the Wide Deadband Mode entry point is used, "R61CNTR" is checked to be sure P20 will not update command rates for at least one second. "R61CNTR" will be checked every 0.5 sec until this condition is met. This condition will be met within 2 seconds or less as long as P20 is running or Note 3 of the procedures is followed. Thereafter, EMP SL-51 does everything described for the +X translation/CMG desaturation entry point and in addition sets relevant phase plane parameters to appropriate Wide Deadband values.

The restoration entry point is used when it is desired to restore the DAP to a conventional configuration. When this entry point is used, the EMP zeros the double precision WBODYs and restores to nominal values all phase plane parameters altered by use of either of the above mentioned entry points. This means that when this restoration entry point is used subsequent to use of the EMP for +X translation or CMG desaturation, some of the parameters are reloaded with values that they already have. This activity is superfluous but harmless.

ASSUMPTIONS:

- 1. Docked DAP is on and properly loaded with nominal mission pad loads.
- 2. Program coding has been uplinked via P27.

RESTRICTIONS AND LIMITATIONS:

- The initiation options of EMP SL-51 will not work in HOLD or FREE control mode, unless the IMU off procedures are used. (Steps 5a and 5b of procedure A and steps 4a and 4b of procedures B.)
- The +X translation/CMG desaturation option of EMP SL-51 is designed to work in POO and P47 only.
- 3. The Wide Deadband Mode initiation option is designed to work only in POO or with options 1, 2 or 5 of P20 running in the background. If this option is to be used in POO, location E6,1776 (ECADR 3376) should be loaded with a positive number greater than or equal to 2.
- 4. Total ground-or crew-computed rate should not exceed 0.4 degree/sec.
- When EMP SL-51 is used in conjunction with CMG desaturation, the TACS must be in an inactive or FREE drift type mode.
- 6. When EMP SL-51 is used in conjunction with +X translation or Wide Deadband Mode initiation, all OWS control systems (CMGs and TACS) must be in an inactive or FREE drift type mode.
- 7. The +X Translation and CMG Desaturation PROCEDURES can be modified to work with the IMU power off. Since the Wide Deadband Mode assumes active attitude control, it is pointless to attempt Wide Deadband initiation with the IMU off. The Restoration Option can be used with or without the IMU power on.
- 8. If a VERB 37 major mode change or a restart occurs following the uplink of EMP SL-51 coding and before VERB 30 ENTR, VAC area 4 should be checked to ensure that the program code is intact.
- 9. When EMP SL-51 is used in conjunction with +X translation with the IMU on, the VERB 30 ENTR must be keyed 5 or more seconds before switching to FREE prior to +X translation.

PROCEDURES:

A. +X TRANSLATION

- 1. Maneuver to burn attitude.
- 2. Load double precision desired rates into registers 1372 through 1377. (See notes (2), (3), and (4) listed at the end of the uplink).
- 3. Key VERB 5 NOUN 26 ENTR and verify that NOUN 26 is valid for this option of EMP SL-51:

R1 14000

R2 00620

R3 00006

- 4. S/C CONT CMC
- 5. CMC MODE AUTO

If the IMU is not on, perform the following steps:

5a. Load C31FLWRD: (to set DAP mode CMC-AUTO when IMU power is off).

Key-

VERB 21 NOUN 1 ENTR

373 ENTR

30000 ENTR

5b. Load IMODES 33: (to remove DAP disable due to IMU off).

Key-

VERB 21 NOUN 1 ENTR

1324 ENTR

26000 ENTR

6. At TIG-6 seconds,

Key-

VERB 30 ENTR

to initiate EMP SL-51.

7. At TIG-1 seconds,
CMC MODE - FREE.
If IMU is not on, Step 7 is not required.

NOTE1.—If after Step 7 the CMC MODE switch is returned to either AUTO or HOLD, the DAP will perform an effective attitude hold function with a zero command rate and will use the deadband and WLH/SLOP+1 loaded by EMP SL-51. If IMU is not on, Note 1 does not apply.

- 8. At TIG, perform +X translational maneuver.
- Reconfigure the Docked DAP by using procedure D of EMP SL-51.

NOTE2.—Attitude control of the OA will normally be taken over by the CMGs after step 9.

B, CMG DESATURATION

- 1. Load double precision desired rates into registers 1372 through 1377. (See notes (2), (3), and (4) listed at the end of the uplink).
- 2. Key VERB 5 NOUN 26 ENTR and verify that NOUN 26 is valid for this option of EMP SL-51:

R1 14000

R2 00620

R3 00006

- 3. S/C CONT CMC
- 4. CMC MODE AUTO

If the IMU is not on, perform the following steps:

4a. Load C31FLWRD: (to set DAP mode CMC-AUTO when IMU power is off).

Key— VERB 21 NOUN 1 ENTR 373 ENTR 30000 ENTR

4b. Load IMODES 33: (to remove DAP disable due to IMU off).

Key-

VERB 21 NOUN 1 ENTR 1324 ENTR 26000 ENTR

- 5. Key VERB 30 ENTR to initiate EMP SL-51.
- 6. Reconfigure the Docked DAP by using procedure D of EMP SL-51.

C. WIDE DEADBAND MODE INITIATION

- 1. Load double precision desired rates into register 1372 through 1377. (See notes (2), (3), and (4) listed at the end of the uplink).
- 2. Initiate P20 if it has not already been initiated.

NOTE3.—If P20 is not to run in the background:

Load R61 CNTR:
Key—
VERB 21 NOUN 1 ENTR
3376 ENTR
2 ENTR

3. Key VERB 5 NOUN 26 ENTR and verify that NOUN 26 is valid for this option of EMP SL-51:

R1 14000

R2 00611

R3 00006

- 4. S/C CONT CMC
- 5. CMC MODE AUTO
- 6. Key VERB 30 ENTR to initiate EMP SL-51.
- 7. When the Wide Deadband Mode is no longer desired perform procedure D to restore the DAP to a conventional configuration.

D. RESTORATION OPTION

 Key VERB 5 NOUN 26 ENTR and verify that NOUN 26 is valid for this option of EMP SL-51:

> R1 14000 R2 00653 R3 00006

CMC MODE - FREE
 If IMU is not on, Step 2 is not required.

3. Key VERB 30 ENTR to initiate EMP SL-51.

NOTE4.—Desired activity can be resumed at any time after step 3.

RECOVERY/ TERMINATION:

- 1. The restoration procedure of EMP SL-51 is the standard recovery.
- 2. EMP SL-51 is not restart protected. If a restart occurs in Step 6 of +X translation procedures, Step 5 of CMG Desaturation procedures, or Step 3 of the Restoration procedures simply repeat the step. In the +X translation procedures this may force a TIG slip. If a restart occurs in step 6 of the Wide Deadband Mode initiation, execute the Restoration Option of EMP SL-51 and then repeat the Wide Deadband Mode initiation procedures in their entirety.

| ECADR | Tag | Coo | de | Octal |
|--|-----------------------|--|---|---|
| 0605 0606 0607 0610 | WAIT | CAF TC CADR CADR | .5SEC BANKCALL E/BKCALL DELAYJOB | 35023 04647 24000 01731 |
| 0610 0611 0612 0613 0614 0615 0616 | WDBSTART | CADR CS AD CCS TC TC TC TC | ONE R61CNTR A RATESTRT WAIT WAIT WAIT | 45001 61776 10000 00620 00605 00605 |
| 0620 0621 0622 0623 0624 | RATESTRT | CA TS TS CAF TS | DDB ADB DBPTC EBANK5 EBANK ZAP1 | 31370 55706 55775 35055 54003 01400 |
| 0625 0626 0627 0630 0631 0632 0633 0634 0635 0636 0637 0640 0641 0642 0643 0644 0645 0646 0647 0651 | ZAP2 | TC CA TS CA TS CA TS CAF TC ADRES ADRES CA TS CA | E6SETTER CDUX CDUXD CDUY CDUYD CDUZ CDUZD FIVE GENTRAN EXES WBODY FFB CH31TEMP HIGH9 HOLDFLAG EBANK5 EBANK ZAP3 00000 | 04611 30032 55677 30033 55701 30034 55703 35004 05562 01372 01554 31367 55663 37677 55330 00003 35055 54003 01411 00000 |
| 0652 0653 0654 0655 0656 0657 | RESTORE | OCT CA TS CA TS TC | 00000 ONE HOLDFLAG EBANK5 EBANK RESTORE1 | 00000 35001 55330 35055 54003 01472 |
| 1016 1017 1020 | | OCT OCT OCT | 14000 ABC 00006 | 14000 00ABC(1) 00006 |
| 1366 1367 1370 | RSTRTAD FFB DDB | ECADR OCT OCT | RATESTRT 37752 02660 | 00620 37752 02660 |

| 1371 | | OCT | 00000 | 00000 |
|--------------|---|----------------|---------------|----------------|
| 1372 | EXES | OCT | XXXXX | XXXXX(2) |
| 1373 | 21120 | OCT | XXXXX | XXXXX(2) |
| 1374 | WISE | OCT | YYYYY | YYYYY(3) |
| 1375 | ,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,, | OCT | YYYYY | YYYYY(3) |
| 1376 | ZEEZ | OCT | ZZZZZ | ZZZZZ(4) |
| 1377 | | OCT | ZZZZZ | ZZZZZZ(4) |
| 10 | | | | |
| 2400 | ZAP1 | TC | INTPRET | 06006 |
| 2401 | | DLOAD | | 77745 |
| 2402 | | | WLSDUM | 02463 |
| 2403 | | STORE | WLH/SLOP | 03034 |
| 2404 | | VLOAD | | 77775 |
| 2405 | | | ZEROVEC | 15726 |
| 2406 | | STORE | DELCDUX | 03227 |
| 2407 | | EXIT | | 77776 |
| 2410 | | TC | ZAP2 | 00626 |
| 2411 | ZAP3 | CS | N26/2CAD | 41017 |
| 2412 | | AD | RSTRTAD | 61366 |
| 2413 | | EXTEND | | 00006 |
| 2414 | | BZF | ENDOFJOB | 15220 |
| 2415 | | CAF | 1SEC | 35030 |
| 2416 | | TC | BANKCALL | 04647 |
| 2417 | | CADR | E/BKCALL | 24000 |
| 2420 | | CADR | DELAYJOB | 01731 |
| 2421 | | TC | INTPRET | 06006 |
| 2422 | | DLOAD | ar ananyina a | 77745 |
| 2423 | | CEODE | SL2P1DUM - 1 | 02461 |
| 2424 | | STORE | SLOPE - 1 | 03305 |
| 2425 | | VLOAD | Cr opening | 77775 |
| 2426 | | CMODE | SL2P1DUM | 02462 03033 |
| 2427 | | STORE TLOAD | SLOPE2 + 1 | 77751 |
| 2430 | | ILOAD | ECYWWDB | 02470 |
| 2431 | | STORE | ECYW | 03041 |
| 2432 2433 | | TLOAD | EC I W | 77751 |
| 2434 | | ILOAD | JDM | 02456 |
| 2435 | | STORE | J/M | 03255 |
| 2436 | | EXIT | 0 / 141 | 77776 |
| 2437 | | TC | ENDOFJOB | 05220 |
| 2401 | | 10 | Embor oob | 00200 |
| 2455 | JDM | OCT | 0231 | 00231 |
| 2456 | | OCT | 0231 | 00231 |
| 2457 | | OCT | 0231 | 00231 |
| 2460 | BIGZ | OCT | 00000 | 00000 |
| 2461 | SL2P1DUM | OCT | 00024 | 00024 |
| 2462 | WLSDUM | OCT | 00114 | 00114 |
| 2463 | | OCT | 10707 | 10707 |
| 2464 | | OCT | 00055 | 00055 |
| 2465 | | OCT | 02755 | 02755 |
| 2466 | | OCT | 37777 | 37777 |
| 2467 | ECYWWDB | OCT | 40000 | 40000 |
| 2470 | | OCT | 00000 | 00000 |
| 2471 | D DOMO D DA | OCT | 00000 | 00000 |
| 2472 | RESTORE1 | TC | INTPRET | 06006 |
| 2473 | | VLOAD | SL2P1R | 77775 02526 |
| 2474 | | STODE | SLOPE2 + 1 | 03033 |
| 2475 | | STORE TLOAD | SLOPE2 + 1 | 77751 |
| 2476 2477 | | ILOAD | ECYWR | 02534 |
| 2500 | | STORE | ECYW | 03041 |
| 2000 | | 210111 | 2011 | 20011 |

| 2501 | | TLOAD | | 77751 |
|-------|----------|--------|-------------|-------|
| 2502 | | | J/MDCKD | 03047 |
| 2503 | | STORE | J/M | 03255 |
| 2504 | | VLOAD | | 77775 |
| 2505 | | | ZEROVEC | 15726 |
| 2506 | | STORE | WBODY | 03155 |
| 2507 | | SLOAD | WEGET | 77735 |
| 2510 | | OBOILD | DKDB | 03075 |
| 2511 | | STORE | ADBR | 02540 |
| 2512 | | STORE | ADBRP2 | 02542 |
| 2513 | | DLOAD | IIDDI(1 2 | 77745 |
| 2514 | | DECIE | JUNKER | 02541 |
| 2515 | | STORE | RATEPTC | 03375 |
| 2516 | | DLOAD | 1(211 11 10 | 77745 |
| 2517 | | DECIL | SLOPER | 02537 |
| 25 20 | | STORE | SLOPE | 03306 |
| 2521 | | EXIT | опот п | 77776 |
| 2522 | | TC | ENDOFJOB | 05220 |
| 2523 | | OCT | 00000 | 00000 |
| 2523 | | OCT | 00000 | 00000 |
| 2524 | | OCI | 00000 | |
| 2525 | SL2P1R | OCT | 07534 | 07534 |
| 2526 | | OCT | 00114 | 00114 |
| 2527 | | OCT | 00056 | 00056 |
| 2530 | | OCT | 00055 | 00055 |
| 2531 | | OCT | 00017 | 00017 |
| 2532 | | OCT | 05225 | 05225 |
| 2533 | ECYWR | OCT | 72616 | 72616 |
| 2534 | | OCT | 66670 | 66670 |
| 2535 | | OCT | 24434 | 24434 |
| 2536 | SLOPER | OCT | 03656 | 03656 |
| 2537 | ADBR | OCT | 03000 | 03000 |
| 2540 | JUNKER | OCT | 00000 | 00000 |
| 2541 | ADBRP2 | OCT | 03000 | 03000 |
| 2542 | JUNKERP2 | OCT | 00000 | 00000 |

See notes () listed at the end of the uplink.

UPLINK:

For loading EMP SL-51 is as follows:

| Load 1 | Load 2 | Load 3 | Load 4 | Load 5 |
|--------|--------|--------------|---------|------------|
| V71E | V71E | V71E | V71E | V71E |
| 24E | 24E | 11E | 5 E | 14E |
| 605E | 627E | 651E | 1016E | 1366E |
| 35023E | 30032E | \mathbf{E} | 14000E | 620E |
| 4647E | 55677E | E | ABCE(1) | 37752E |
| 24000E | 30033E | 35001E | 6E | 2660E |
| 1731E | 55701E | 55330E | V33E | E |
| 45001E | 30034E | 35055E | | XXXXXE (2) |
| 61776E | 55703E | 54003E | | XXXXXE (2) |
| 10000E | 35004E | 1472E | | YYYYYE (3) |
| 620E | 5562E | V33E | | YYYYYE (3) |
| 605E | 1372E | | | ZZZZZE (4) |
| 605E | 1554E | | | ZZZZZE (4) |
| 605E | 31367E | | | V33E |
| 31370E | 55663E | | | |
| 55706E | 37677E | | | |
| 55775E | 55330E | | | |
| 35055E | 3E | | | |
| 54003E | 35055E | | | |
| 1400E | 54003E | | | |
| 4611E | 1411E | | | |
| V33E | V33E | | | |
| | | | | |

| Load 6 | Load 7 | Load 8 | Load 9 | Load 10 |
|--------|--------|--------|------------------|---------|
| V71E | V71E | V71E | V71E | V71E |
| 24E | 20 E | 24E | 24E | 24E |
| 2400E | 2422E | 2455E | 2477E | 2521E |
| 6006E | 77745E | 231E | 2534E | 77776E |
| 77745E | 2461E | 231E | 3041E | 5220E |
| 2463E | 3305E | 231E | 77751E | E |
| 3034E | 77775E | E | 3047E | E |
| 77775E | 2462E | 24E | 3255E | 7534E |
| 15726E | 3033E | 114E | 77775E | 114E |
| 3227E | 77751E | 10707E | 15726E | 56E |
| 77776E | 2470E | 55E | 3155E | 55E |
| 626E | 3041E | 2755E | 77735E | 17E |
| 41017E | 77751E | 37777E | 3075E | 5225E |
| 61366E | 2456E | 40000E | 2540E | 72616E |
| 6E | 3255E | E | 2542E | 66670E |
| 15220E | 77776E | E | 77745E | 24434E |
| 35030E | 5220E | 6006E | 2541E | 3656E |
| 4647E | V33E | 77775E | 3375E | 3000E |
| 24000E | | 2526E | 77745E | E |
| 1731E | | 3033E | $2537\mathrm{E}$ | 3000E |
| 6006E | | 77751E | 3306E | E |
| V33E | | V33E | V33E | V33E |

(1) ABC = 611 for Wide Deadband initiation

- (2) XXXXX = Ground-computed desired roll rate, scaled B-3 revs/deci sec, DP.
- (3) YYYYY = Ground-computed desired pitch rate, scaled B-3 revs/deci sec, DP.
- (4) ZZZZZ = Ground-computed desired yaw rate, scaled B-3 revs/deci sec, DP.

^{= 620} for +X Translation and CMG Desaturation

^{= 653} for Restoration

EMP SL-52: CHECKSUM FOR EMPS USING VAC AREA 4

PURPOSE:

EMP SL-52 provides a means of determining whether or not that portion of an EMP previously loaded into VAC area 4 is still intact.

FUNCTION AL DESCRIPTION:

EMP SL-52 does a CHECKSUM of the VAC area 4 registers used by an EMP and gives an alarm (Code 01753) if that EMP is still not intact.

EMPs using VAC area 4 are: SL-23 Monitor Jet-On Failure

SL-28 Monitor Jet-On Failure and Do EMP SL-26 SL-51 Generalized Rotational Rate Generator

ASSUMPTIONS:

- Appropriate EMP has been uplinked in VAC area 4 prior to operation of EMP SL-52.
- 2. EMP SL-52 has been uplinked with appropriate values in location 3756 and 3757. (See table at end of UPLINK.)

RESTRICTIONS AND LIMITATIONS:

- 1. EMP SL-52 shares R27 erasables; therefore activation of R27 will destroy EMP SL-52.
- 2. For EMPs SL-23 and SL-28 the value of -XDEG is not included in this CHECKSUM procedure.

PROCEDURES:

Key VERB 15 NOUN 26 ENTR and verify that NOUN
 26 is valid for EMP SL-52:

R1 14000 R2 01727 R3 00007

- 2. Key VERB 30 ENTR
- If the code in VAC area 4 is verified to be correct, zeros will appear in R1 of NOUN 26.
- 4. If the code in VAC area 4 has been altered, a PROG alarm will result. Key VERB 5 NOUN 9 ENTR to

observe alarm code 1753. New uplink of VAC area ${\bf 4}$ in question should be requested.

SL-23 Loads 1 and 2

SL-28 Loads 1 and 2

SL-51 Loads 1, 2 and 3

RECOVERY/

TERMINATION: NA

ERASABLE MEMORY:

Program coding for EMP SL-52 is as follows:

| | | | | * |
|-------|--------|------|----------|--------|
| ECADR | Tag | C | ode | Octal |
| 3727 | BEGIN | CA | ZERO | 35003 |
| 3730 | | TS | SUM | 55760 |
| 3731 | | TS | SUM+1 | 55761 |
| 3732 | | CA | ICNTR | 31756 |
| 3733 | BACK52 | TS | CNTR52 | 55762 |
| 3734 | | NDX | CNTR52 | 51762 |
| 3735 | | CA | 605 | 30605 |
| 3736 | | TS | L | 54001 |
| 3737 | | CA | ZERO | 35003 |
| 3740 | | DAS | SUM | 21761 |
| 3741 | | CCS | CNTR52 | 11762 |
| 3742 | | TC | BACK52 | 01733 |
| 3743 | | CS | SUM+1 | 41761 |
| 3744 | | AD | CHKSUM | 61757 |
| 3745 | | CCS | A | 10000 |
| 3746 | | TC | +2 | 01750 |
| 3747 | | TC | OK | 01753 |
| 3750 | | TC | ALARM | 05644 |
| 3751 | | TC | OK | 01753 |
| 3752 | | TC | ENDOFJOB | 05220 |
| 3753 | OK | CA | ZERO | 35003 |
| 3754 | | TS | N26/PRI | 55016 |
| 3755 | | TC | ENDOFJOB | 05220 |
| 3756 | ICNTR | OCT | ABCDE | ABCDE* |
| 3757 | CHKSUM | OCT | FGHIJ | FGHIJ* |
| 3760 | SUM | TEMP | | |
| 3761 | SUM+1 | TEMP | | |
| 3762 | CNTR52 | TEMP | | |

 $^{^{*}}$ See table of values given at the end of uplink.

Uplink for loading EMP SL-52 code by P27 is as follows:

UPLINK:

| Load 1 | Load 2 | Load 3 |
|---------------|-------------------|---------------|
| V71E | V71E | V71E |
| 5E | 24 E | 11E |
| 1016E | 3727E | 3751E |
| 14000E | 35003E | 1753E |
| 1727E | 55760E | 522 0E |
| $7\mathrm{E}$ | 55761E | 35003E |
| V33E | $31756\mathrm{E}$ | 55016E |
| | 55762E | 5220E |
| | 51762E | *ABCDEE |
| | 30605E | *FGHIJE |
| | 54001E | V33E |
| | 35003E | |
| | 21761E | |
| | 11762E | |
| | 1733E | |
| | 41761E | |
| | $61757\mathrm{E}$ | |
| | 10000E | |
| | $1750\mathrm{E}$ | |
| | $1753\mathrm{E}$ | |
| | 5644E | |
| | V33E | |

 $^{^{*}}$ Table of values necessary for each of the EMPs using VAC area 4:

| | TAG | ECADR | SL-23 ⁽¹⁾ | SL-28 ⁽¹⁾ | SL-51 |
|-------|--------|-------|----------------------|----------------------|-------|
| ABCDE | ICNTR | 3756 | 36 | 40 | 52 |
| FGHIJ | CHKSUM | 3757 | 23156 | 52610 | 12542 |

 $^{^{(1)}{\}rm EMP~SL}\text{-}52$ does not check -XDEG register, because this register may change depending on the desired allowable excursion beyond the deadband.

SKYLARK 7 (GSOP)

R693

Internal Distribution List

| Group 23A | D. Lutkevich Brand Gustafson Higgins Kachmar Klumpp Kriegsman Levine | DL7-211 Muller Philliou Phillips Pu Robertson Tempelman | (13) |
|-----------|--|---|------|
| Group 23B | C. Taylor Beals Brodeur Cramer Goode Hamilton Haslam Lollar | DL7-211L McCoy Ostanek Rye Smith Whittredge Zeldin Nayar | (14) |
| Group 23B | L. Harris Albert Berman | DL7-238A Millard Schulenberg | (4) |
| Group 23C | M. Erickson Bairnsfather Croopnick Fraser Jones Kalan Engel | DL7-215J Penchuk Schlundt Trunbull Womble Work | (11) |

| Group 23D | S. Ryan Drake Dunbar Groome Johnson | DL7-213 Larson Metzinger Walsh Kibruz | (8) |
|----------------|--|---------------------------------------|-----|
| Group 23H | C. Loury Ogren Kossuth | DL7-272 Fitzgibbons O'Connor | (4) |
| Group 23N | G. Grover Blanchard Johnson | DL11-201 Ogletree Parr | (4) |
| Group 23P | N. Pollack Greene | DL7-252 | (1) |
| Group 23P | B. Hwoschinsky Battin | DL7-203 Copps | (2) |
| Group 23S | P. Amsler Adams Felleman Heinemann Woosley | DL7-140 McOuat Werner White | (7) |
| Group 23S | J. Grinnell Edmonds Grace Kido | DL7-148B Megna St. Amand | (5) |
| Group 33 | F. Harding Drane Glick | DL7-111 David Cook | (4) |
| APOLLO Library | y | | (2) |
| DSDL Technical | Documentation Center | | (2) |

External Distribution List

SKYLARK 1

| Charles Stark Draper Laboratory Code EG/MIT Building 16 NASA Manned Spacecraft Center Houston, Texas 77058 Attn: Mr. G. Silver | (3) |
|--|------|
| NASA MSC HW Building M7-409 Kennedy Space Center Florida 32815 Attn: Mr. F. Hughes | (10) |
| Delco Electronics Division Goleta, California 93017 Attn: Mr. J. Striddle Mr. W. Siarnicki | (2) |
| Delco Electronics Division P.O. Box 21027 Kennedy Space Center Florida 32815 Attn: Mr. J. Kaiser | (2) |
| Delco Electronics Division P.O. Box 374 Downey, California 90241 Attn: Mr. D. Karstedt | (1) |
| Raytheon Company Boston Post Road Sudbury, Mass. 01776 Attn: Mr. R. Zagrodnick | (6) |

| NASA/MSFC | National Aeronautics and Space Administration George C. Marshall Space Flight Center Huntsville, Alabama 35812 | (10) |
|-------------------|--|----------|
| | Attn: J. Mack R-ASTR-5 (1) V. Buckelew S&E-AERO-MFG (1) A. Deaton R-AERO-DG (1) F. Moore R-ASTR-N (1) H. Hosenthien R-ASTR-F (1) D. Germany I-I/B-E (1) R. Barraza I-V-E (1) W. Chubb R-ASTR/NG (1) J. McCullough I-VE/T (1) | |
| NASA/MSC | National Aeronautics and Space Administration Manned Spacecraft Center APOLLO Document Control Group (BM86) Houston, Texas 77058 Attn: Mr. J. Garman, FS6 (letter of transmittal only) | (130+1R) |
| BELLCOMM | Bellcomm, Inc. 1100 17th Street NW Washington, D. C. 20036 Attn: Information Analysis Section | (6) |
| LINK | LINK Group, GPSI SIMCOM 1740 A NASA Boulevard Houston, Texas 77058 Attn: Mr. D. Klingbell | (3) |
| NASA/GSFC | National Aeronautics and Space Administration Goddard Space Flight Center Greenbelt, Maryland 20771 Attn: Mr. P. Pashby, Code 813 | (2) |
| NASA/RASPO NAR | National Aeronautics and Space Administration Resident APOLLO Spacecraft Program Office North American Rockwell, Inc. Space and Information Systems Division CSM Data Management D/096-704 AE99 12214 Lakewood Boulevard Downey, California 90241 | (1+1R) |

| NASA/KSC | National Aeronautics and Space Administration Kennedy Space Center Florida 32899 Attn: Technical Document Control Office | (3) |
|------------------|---|------|
| NASA/RASPO GE | General Electirc Company APOLLO Systems P.O. Box 2500 Daytona Beach, Florida 32015 Attn: Mr. E. P. Padgett, Jr./Unit 509 | (1) |
| NASA/HDQ | NASA Headquarters 600 Independence Avenue SW Washington, D. C. 20546 Attn: Mission Director Code MA (1) Robert Aller, Code MAO (1) | (2) |
| | Robert Arier, Code MAO (1) | |
| NASA/LEWIS | National Aeronautics and Space Administration Lewis Research Center Cleveland, Ohio 44135 Attn: Library | (2) |
| NASA/FRC | National Aeronautics and Space Administration Flight Research Center Edwards AFB, California 93523 Attn: Research Library | (1) |
| NASA/LRC | National Aeronautics and Space Administration Langley Research Center Langley AFB, Virginia 23365 Attn: Mr. A. T. Mattson | (2) |
| NASA/KSC | Kennedy Space Center Florida 32815 M.S.O.B. North American Mail Station ZK69 Attn: Mr. D. Matteson | (1) |
| NASA/WSMR | National Aeronautics and Space Administration Post Office Drawer MM Las Cruces, New Mexico 88001 Attn: RH4 Documentation | (2) |